

## Subdivisional Lines, T 6 S R 33 E W M.

## Chains

A spruce, 15 ins. diam., brs. N.62°W., 16 lks. dist.,  
marked  $\frac{1}{4}$  S B T.

A spruce, 20 ins. diam., brs. S.23°E., 7 lks. dist.,  
marked  $\frac{1}{4}$  S B T.

Descend.

80.00 Set fir post, 4 ft. long, 4 ins. sq., 24 ins. in ground,  
for Cor. to Secs. 27, 28, 33 & 34; marked

T 6 S S 27 on N.E.

R 33 E S 34 on S.E.

S 33 on S.W. and

S 28 on N.W. face, with

1 notch on S. and

3 notches on E. edges, from which

A fir, 16 ins. diam., brs. N.33°E., 19 lks. dist.,  
marked T 6 S R 33 E S 27 B T.

A fir, 8 ins. diam., brs. S.79°E., 31 lks. dist.,  
marked T 6 S R 33 E S 34 B T.

A pine, 13 ins. diam., brs. S.72°W., 7 lks. dist.,  
marked T 6 S R 33 E S 33 B T.

A fir, 11 ins. diam., brs. N.24°W., 11 lks. dist.,  
marked T 6 S R 33 E S 28 B T.

Land; rolling.

Line extends along the Brakes of a high hill, descending  
East.

Soil; 2nd rate.

Densely covered with forests of pine, fir, tamarack & spruce  
timber, 80 chs.

Thick undergrowth of balm, alder, small pine & fir, 80 chs.

E. on random line bet. Secs. 27 & 34.

Var. 20°E.

11.00 Spring branch, 3 lks. wide, course S.E.

12.00 " " " " " " " "

A point, 200 ft. below Sec. Cor.

Thence ascend hill, course N. & S.