

Subdivisional Lines, T 6 S R 33 E W M.

Chains

A fir, 10 ins. diam., brs. S.45°E., 29 lks. dist.,
marked T 6 S R 33 E S 22 B T.

A fir, 10 ins. diam., brs. S.23°W., 11 lks. dist.,
marked T 6 S R 33 E S 21 B T.

Dug pits, 18 x 18 x 12 ins. in Sec. 16, 5½ ft. dist., and
raised mound of earth around post.

Land; gently rolling.

Soil; good 2nd rate.

Densely covered with forests of fir & black pine timber,
80 chs.

E. on random line bet. Secs. 15 & 22.

Var. 19°10'E.

24.80 Ravine, course N.

40.00 A point, 200 ft. below last Sec. Cor. & set temp. ¼ Sec.
Cor.

Descend hill, course N.E.

57.00 Trail, course N.W. & S.E.

80.00 Intersect N. & S. line at 8 lks. N. of Cor. to Secs. 14,
15, 22 & 23.

Thence I run

N.89°57'W. on true line bet. Secs. 15 & 22.

With same Var.

40.00 Set basalt stone, 18 x 11 x 3 ins., 12 ins. in ground, for
¼ Sec. Cor., marked ¼ on N. face, from which

A fir, 20 ins. diam., brs. S. 3 lks. dist., marked ¼
S B T.

A fir, 18 ins. diam., brs. N.74°E., 9 lks. dist.,
marked ¼ S B T.

80.00 The Cor. to Secs. 15, 16, 21 & 22.

Land; rolling & hilly.

Soil; 2nd rate.

Densely covered with forests of pine, fir, tamarack & and
spruce.

Undergrowth of small spruce & pine, 80 chs.