

## Subdivisional Lines, T 6 S R 33 E W M.

## Chains.

Land; gently rolling.

Soil; 2nd rate.

Densely covered with forests of pine & fir, 76.78 chs.

July 6th, 1883.

N. bet. Secs. 7 & 8.

Var. 23°E

Descend hillside, facing N. W.

29.50 Foot of hill & spring branch, 3 lks. wide, course N.E.

40.00 Set basalt stone, 12 x 8 x 6 ins., 8 ins. in ground, for

$\frac{1}{4}$  Sec. Cor., marked  $\frac{1}{4}$  on W. face, from which

A pine, 30 ins. diam., brs. E., 18 lks. dist., marked

$\frac{1}{4}$  S B T.

A pine, 24 ins. diam., brs. S.69°W., 23 lks. dist.,

marked  $\frac{1}{4}$  S B T.

46.00 Top of ascent, from branch, course W. & S.E.

Descend.

80.00 Set basalt stone, 12 x 8 x 7 ins., 8 ins. in ground, for

Cor. to Secs. 5, 6, 7, & 8, marked with 5 notches on  
S & E edges, from which

A pine, 8 ins. diam., brs. N.58°E., 32 lks. dist.,

marked T 6 S R 33 E S 5 B T.

A fir, 24 ins. diam., brs. S.24°E., 44 lks. dist.,

marked T 6 S R 33 E S 8 B T.

A fir, 24 ins. diam., brs. S.30°W., 34 lks. dist.,

marked T 6 S R 33 E S 7 B T.

A fir, 24 ins. diam., brs. N.48°W., 56 lks. dist.,

marked T 6 S R 33 E S 6 B T.

Land; hilly.

Soil; 2nd rate.

Densely covered with forests of pine, fir & tamarack tim-  
ber, 80 chs.

Occasional thickets of pine undergrowth.

E. on random line bet. Secs. 5 & 8.

Slope facing N.E.

Var. 20°E.