

Subdivisional Lines, T 6 S R 34 E W M.

Chains

A spruce, 12 ins. diam., brs. S.67°E., 50 lks. dist.,
marked T 6 S R 34 E S 2 B T.

A pine, 10 ins. diam., brs. S.31°W., 34 lks. dist.,
marked T 6 S R 34 E S 3 B T.

Land; hilly.

Soil; 2nd rate.

Densely covered with forests of pine, fir & spruce, 61.56 chs.

Thick undergrowth of small pine & huckleberry, 61.56 chs.

July 25, 1883.

From the Cor. to Secs. 3, 4, 33 & 34 on S. Bdy. of Tp.,
which is a pine, 10 ins. diam., marked

T 6 S S 34 on N.E.

R 34 E S 3 on S.E.

T 7 S S 4 on S.W. and

S 33 on N.W. faces, with

3 notches on E. and W. edges;

from which

A pine, 6 ins. diam., brs. N.42°E., 30 lks. dist.,
marked T 6 S R 34 E S 34 B T.

A pine, 6 ins. diam., brs. S.39°E., 21 lks. dist.,
marked T 7 S R 34 E S 3 B T.

A spruce, 18 ins. diam., brs. S.65°W., 20 lks. dist.,
marked T 7 S R 34 E S 4 B T.

A spruce, 15 ins. diam., brs. N.37°W., 29 lks. dist.,
marked T 6 S R 34 E S 33 B T.

I run

N. bet. Secs. 33 & 34.

Var. 19°E.

Descend hillside facing NW

14.00 Ravine, course N.W.

29.15 Trail, course N.W. & S.E.

40.00 A point, 250 ft. below last Sec. Cor. and

Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground,
for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on W. face; from which