

South Bdy., T 6 S R 35 E W M.

Chains

1 notch on W. edges, from which,

A pine, 6 ins. diam., brs. N.60°E., 18 lks. dist.,
marked T 6 S R 35 E S 32 B T.

A pine, 7 ins. diam., brs. N.82°W., 11 lks. dist.,
marked T 6 S R 35 E S 31 B T.

Land; high & broken.

Soil; 2nd rate.

Densely covered with forests of pine, fir & tamarack, 60.63
chains.

S.89°39'E. on true line on S. Bdy. of Sec. 32.

Var. 20 $\frac{1}{4}$ °E.

40.00 Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$
Sec. Cor., marked $\frac{1}{4}$ on N. face, from which

A pine, 7 ins. diam., brs. N.82°W., 16 lks. dist.,
marked $\frac{1}{4}$ S B T.

A pine, 6 ins. diam., brs. S.55°E., 17 lks. dist.,
marked $\frac{1}{4}$ S B T.

80.00 Set basalt stone, 14 x 10 x 6 ins., 9 ins. in ground, for
Cor. to Secs. 32 & 33, marked with 4 notches on E. and
2 notches on W. edges, from which

A pine, 20 ins. diam., brs. N.58°E., 80 lks. dist.,
marked T 6 S R 35 E S 33 B T.

A pine, 18 ins. diam., brs. N.65°W., 7 lks. dist.,
marked T 6 S R 35 E S 32 B T.

Land; high & rolling.

Soil; 2nd rate.

Densely covered with forests of pine, fir & tamarack, 80 chs.
Sept. 1, 1884.

Resurvey N. Bdy. T 7 S., R 35 E., W. M.
As surveyed by same U.S. Dept. Surveyor,
Under same Contract & date.

As the E. Bdy. of T 7 S., R. 35 E. has been resurveyed by me
and a portion of the line found to have a bearing N.0°
54'W., so that it makes a departure to the W. of 1.60 chs.