

## Resurvey N. Bdy., T 7 S R 35 E W M.

## Chains

- 1.60 The Cor. to Secs. 31 & 32, T 6 S R 35 E.
- 41.61 The  $\frac{1}{4}$  Sec. Cor.
- 62.24 The Cor. to Tps. 6 & 7 S., Rs. 34 & 35 E.  
Land; high & broken,  
Soil; 2nd rate.  
Densely covered with forests of pine, fir & tamarack,  
62.24 chs.  
Sept. 3, 1884.
- 
- Subdivisional Lines, T 6 S R 35 E., W.M.  
As surveyed by the same U.S. Dept. Surveyor,  
Under same Contract and Date.
- 
- N. bet. Secs. 32 & 33.  
Var.  $20\frac{1}{2}^{\circ}$  E.  
Ascend through timber.
- 40.00 Set basalt stone, 17 x 10 x 4 ins., 11 ins. in ground, for  
 $\frac{1}{4}$  Sec. Cor., marked  $\frac{1}{4}$  on W. face, from which  
A black pine, 10 ins. diam., brs. S.  $45^{\circ}$  E., 88 lks. dist.,  
marked  $\frac{1}{4}$  S B T.  
A black pine, 8 ins. diam., brs. N.  $88^{\circ}$  W., 61 lks. dist.,  
marked  $\frac{1}{4}$  S B T.
- 45.00 Top of ridge, about 400 ft. above Sec. Cor., course W.  
Descend about 400 ft. to
- 80.00 Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for  
Cor. to Secs. 28, 29, 32 & 33, marked  
T 6 S S 28 on N.E.  
R 35 E S 33 on S.E.  
S 32 on S.W. and  
S 29 on N.W. faces, with  
4 notches on E. and  
1 notch on S. edges,  
from which  
A black pine, 9 ins. diam., brs. N.  $69^{\circ}$  E., 5 lks. dist.,  
marked T 6 S R 35 E S 28 B T.  
A black pine, 8 ins. diam., brs. S.  $58^{\circ}$  E., 10 lks. dist.,  
marked T 6 S R 35 E S 33 B T.