

Subdivisional Lines, T 6 S R 35 E W M.

Chains	E. on random line bet. Secs. 20 & 29. Var. $20\frac{1}{2}^{\circ}$ E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.72	Intersect N. & S. line, 70 lks. N. of Cor. to Secs. 20, 21, 28 & 29. Thence I run N. $89^{\circ}30'$ W. on true lien bet. Secs. 20 & 29. Var. $20\frac{1}{2}^{\circ}$ E.
	Through timber.
.75	A spring branch, 3 lks. wide, runs S.E. Ascend about 500 ft. to
25.00	Top of divide, course S.
39.86	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on N. face, from which A black pine, 6 ins. diam., brs. N. 35° W., 12 lks. dist., marked $\frac{1}{4}$ S B T. A black pine, 12 ins. diam., brs. S. 25° W., 14 lks. dist., marked $\frac{1}{4}$ SBT.
76.25	A creek, 7 lks. wide, runs S., about 350 ft. below divide.
79.72	The Cor. to Secs. 19, 20, 29 & 30. Land; mountainous, 79.72 chs. Soil; 2nd rate. Densely covered with forests of black pine, fir & tamarack, 79.72 chs.
	W. on random line bet. Secs. 19 & 30. Var. $20\frac{1}{2}^{\circ}$ E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
60.40	Intersect W. Bdy. of Tp., 53 lks. S. of Cor. to Secs. 19, 30, 24 & 25, which is a post, 4 ft. long, 4 ins. sq., set firmly in the ground, marked T 6 S S 19 on N.E. R 35 E S 30 on S.E. R 34 E S 25 on S.W. and S 24 on N.W. faces, with