

PLAT AND RECORD OF SURVEY No. 519

Course Degrees Minutes Chains Links

Request of F.J. More & Co.
 Sec 14
 T. 5 N R. 35 E
 Jan'y 26, 27, 28, 1850

W. C. Biron & R. Kinney

being duly sworn as chainmen I proceeded to bisect the above section. For my initial point I took the $\frac{1}{4}$ Gov post on SE boundary of said Sec. The same being in a good state of preservation. From which I run - Var 22' East

South 00 00 100 00 Set Temp Cor for Cent of Section
 " " " 80 00 Failed to find any trace of $\frac{1}{4}$ post on South line of Sec 14. To establish it I went to SE cor of Sec 23 T 5 N R 35 East it being the nearest point from which I could proceed to establish lost corners. To perpetuate SE cor of 23 I buried Coal, basalt rock 6 x 8 x 9 + dug pits raised around etc. From which I run Var 22' East

North 00 00 40 05 Finding a resemblance to pits I dug up char coal + end of charred balun slate same being evidence of original Gov $\frac{1}{4}$ post. Witness W. C. Biron R. Kinney Sam. Richie F. J. More + Sol Whitley. To perpetuate said corner I raised around dug pits etc. From which I run

North - 80 15 Set Temp corner in Switzer's field all evidence of original cor being dug up, or ploughed up. Corner claimed by Switzer being 20 rods from line and bearing no evidence of Government work I could not recognize it.

" - 40 00 Set Temp $\frac{1}{4}$ post on East line of 14
 " - 80 00 " " Cor for Secs 11-12-13-14 Temp Cor being 30 rods East of Cor East by J. H. Stinson

PLAT AND RECORD OF SURVEY No. 37

J J Merie Et Al Continued

Course	Degrees	Minutes	Chains	Links	
					Shadows being out of line and its location being determined by Simple East + South distances from uncertain corner I deem it illegal From last temp Cor I continue North Var. 22° East
North	-		40	00	Set temp Cor for 1/4 post on East line of Sec 11 it occurring on steep hill side no trace of Gov Cor.
"	-		83	08	Intersect E + N line 4 chains + 40 links East of Gov Corner at Cor of Kirklands land said Cor being in good preservation Having made calculation I returned and made the following corrections on corner between the S.E. Cor of Sec 23 + N.E. Cor of Sec 14. Moved temp Cor of Sec 11-12-13+14
West			2	84	
"			1	76	One fourth post on E line of Sec 14 -
"			88		Cor of Sec 13-14-23+24 - and established corners at the above places by digging pits raising mounds &c.
					To Establish cross lines I went to Gov - Cor of 15-19-18+24 - + run East Var 21° 30' E
West	00	00	40	00	At Cor claimed I found no pits no mound no indication of Gov work hence did not recognize it as Gov Corner.
"	"	"	80	00	Set temp Sec Cor on E + N line for 13-14-23+24
"	"	"	40	00	" " 1/4 " " S line of 14 -
"	"	"	80	00	" " Sec " " 14-15-22+23
"	"	"	40	00	" " 1/4 " at recognized Gov Cor as evidence of same I dug up End of chanced slate road pits &c. Having unselected N + S line 75 links North of said Gov 1/4 post. My correction is 15 links per 1/2 mile

PLAT AND RECORD OF SURVEY No. 57

Course. Degree. Minutes. Chains. Links.

J. J. Hoyle Et. Al. Continued

After making this correction I set permanent $\frac{1}{4}$ Post. Dug pits raised mound etc.

To establish $\frac{1}{4}$ post on West line of Sec 14 - I set on S W cor of Sec as established by me and run *Var. 21° 40' East*

North - - 40 00

And failing to find any indication of Gov. work. I set temp post + run

" - - 84 27

I intersect Gov cor mound and pits visible. for better evidence I dug up end of charred stake. Coal etc.

My correction for $\frac{1}{4}$ post is North 2 R + $13\frac{1}{2}$ L. Having returned and made this correction I set permanent $\frac{1}{4}$ post by burying basalt rock 18 x 20 and raising mound digging pits etc.

After establishing permanent $\frac{1}{4}$ post on South line of Sec 14 I find that first correction for temporary center post set is 6 Rods + $14\frac{1}{2}$ links west. To establish permanent center post I run from the $\frac{1}{4}$ post on East line of Sec 14 *Var 19° 30' East*

West - - 40 00

Set temporary center

" - - 75 30

Intersect the West line 4 Rods + 15 links South of post set. Hence temp post should go North 2 Rods + $7\frac{1}{2}$ links.

I returned to center of Section and set permanent post at the intersection of the two corrected lines as per plat on the following page

