

PLAT AND RECORD OF SURVEY No. ~~111~~

Field Note of a Survey made for
the subdivision of Sec 11 T 2 N R 32 E
Willamette Meridian Aug 25-27 1881 by
H. O. Chapman Deputy County Surveyor

Open Glade sworn Compassman

John Martin

Henry Boyes } sworn Chainmen

Being unable to identify the corner to Secs
2, 3, 10 + 11 I commenced at a stone in a mound
said mound being the original quarter section
corner between 10 + 8 - from which I ran

East 13163% feet To the corner to Secs 1 + 2 on
the township line, Making thorough search
for Government corners at given distances with
unfavorable results, The corner to 1 + 12 was
identified by one B Barren who had pulled
up the stake and had it cached away I
however found the mound with staked
in it and one witness tree, I then divided up this
distance in proportion to the distances given in
the field notes of the original survey,
Running from the initial point as given above
I set temporary corners as follows

East 2628% feet - Set corner to Secs 2, 3, 10 + 11

" 5274 " Quarter Section corner bet 2 + 11

" 7919% " Corner to Secs 1 + 2 on the township line
I then commenced at a stone in a mound with
pile being the original Quarter Sec corner between
Secs 10 + 11 and ran

North 5272% feet to a stone in mound with pile
being the original quarter sec corner between
Secs 2 + 3 T 2 N R 32 E

PLAT AND RECORD OF SURVEY No. 7119

Sec 11 Continued

I then set a stone with Babbitt metal point between the two corners last above mentioned midway (and preserving the distances on an East & West line as above given for the permanent corner to secs 2, 8, 10 & 11

I then commenced at the quarter sec corner between secs 11 & 12 which I identified as the original corner by well formed mound with pits and run

5310^{feet} To a rock in a mound but this corner had been tramped down so much that I run on to

7940^{feet} To mound with pits at corner of fence which verified the stone as being the original quarter section corner.

I then divided the distance and set an oak stake for temporary witness post to true corner 59 feet East of true corner.

I now set the interior quarter section corner by intersecting lines between exterior quarter section corners. The remainder of the work will be easily understood from the accompanying diagram.

I hereby certify that the above are the field notes of a survey made by me for the subdivision of Sec 11 T2 N R32 E Aug 25-27 1881

J. W. Reavis County Surveyor
By H. D. Chapman
Deputy

Recorded Sept 18th 1881

J. H. Raley
County Surveyor