

A. J. Cochran Et. Al.

March 3<sup>rd</sup> 1841

Township 3 N. Range 34 East  
 after qualifying J. H. Kirby and L. M. Waters  
 as chainmen, and W. H. Ferguson + Theo. Kump  
 as flagmen, I used following plan to  
 establish lost corners on North bdy of Town-  
 ship 3 N. R. 34 E.

Went to North West cor of Sec 1 T3NR34  
 it being the nearest visible Gov cor found  
 pits, mound, and Post plain to perpetuate  
 same thru up mound - Run

Course	Degrees	Minutes	Chains	Links	Description	Remarks
East (N)	21	30	40	02	Found well defined Quarter post	Var. 21° 30'
"	"	"	80	01	Found well defined Sec cor. of 2 <sup>nd</sup> 2 <sup>nd</sup> 3	
"	"	"	40	00	Found well defined Quarter Post	
"	"	"	80	"	Ground Ploughed up no indications of Gov Work	
"	"	"	40	"	" " " " " " " "	
"	"	"	79	96	Found well defined pits. to prove the same I dug up end of Balun post with charcoal which was satisfactory evidence of Gov corner. (Witnesses L. M. Waters, J. H. Kirby, Andy Cochran, Alex. McKinnis Theo. Kump, W. H. Ferguson John Morrison) To perpetuate the same I buried Basalt rock 12x6x 8, several pieces of brown glass + set a yew post from thence I run	Var 21° East

East (N)	21	"	39	77	Found well defined Quarter post - as evidence I dug up end of charred Balun post (Witnesses W. H. Ferguson Robt. Hannus, L. M. Waters A. J. Cochran J. H. Kirby J. M. Linnell) To perpetuate the same I buried three Basalt rocks marked one of them thus # set post and raised mound dug pits &c. from this corner I continued	
----------	----	---	----	----	---	--

A. J. Cochran Et. Al. Cont.

Course	Degrees	Minutes	Chains	Links	
East (N <sup>o</sup> 1)	00	00	40	00	Set temp cor. being <sup>Var. 20°</sup> no signs of Gov works. Grounds having been washed away by action of grease water.
East (N <sup>o</sup> 2)	00	00	50	00	No signs of Gov corners having been a sheep corral where corner formerly stood. Set temp corner and continued
East (N <sup>o</sup> 3)	00	00	40	65	Entered West bay of the township at a point 2 1/2 links North of the Township corner. My correction is 7/8 links to 40 chains I returned and set temp cor for 5+6 91+32 7/8 links South of first temp corner set. And Quarter post on North line of Sec 6 - 14 + 2/3 links South of first temp cor. To establish the N.W. cor of Sec 5 I went to the N.W. cor of Sec 32 74 2/3 34 6 and finding pile Gov Post and mound well defined I run on To establish the N.W. cor of Sec 5 I went to the N.W. cor of Sec 32 74 2/3 34 6 and finding pile Gov Post and mound well defined I run on
South	00	00	40	01	Found some indications of Gov works and upon digging found End of charred stave charcoal etc. to perpetuate said corner I set post raised mound dug pile etc. Witnesses L. M. Waters J. H. Kirby A. J. Cochran M. Jenkins. Continued on same line
South	00	00	50	01	Set temp cor at crossing of E + West line
"	00	00	40	00	" " " No indications of Gov works
"	00	00	50	00	Found Gov cor as evidence dug up charred stave coal etc. Witnesses L. M. Waters J. H. Kirby W. H. Ferguson Rott Warren J. A. Sawaller To perpetuate said corner I set Basalt rock 10 x 8 x 7 raised mound dug pile. Having intersected the Sec line S. Rods + 24 1/2 East of Sec cor my cor is 1 R + 8 links to 40 chains To the west having made this correction I

## PLAT AND RECORD OF SURVEY No. 1257

A. J. Cochran Et Al. Cont

I returned and set Quarter post on West line of Sec 5 and set Sec Cor at NE Cor of Sec 6 in a wash cut, set fire post buried horseshoe and set stone marked # dug pits raised mound etc as per instructions  
Witnesses L M Walter John Adams J H Kirby, J W. Siewallen.

To Establish Quarter post on North boundary of Sec 6 I chained 40 chains from Sec Cor of S. E. 31, + 32 on a true line to sec cor on Township line and set Basalt rock in mound of earth in the center of the road. Witnesses J. H. Kirby L M Walter J W. Siewallen, J W Siewallen having been qualified as chainman to assist J. H. Kirby.

To Establish South East Cor of Sec 5 I went to Gov Cor at N. E. Cor of Said Sec and

South 00 00 40 00 No signs of Gov work I set temp post and continued on same line

" " " 80 00 No signs of Gov work I set temp post

" " " 40 00 " " " " " " " "

" " " 86 55 I intersect E + W line 10 Rods + 14 links East of well defined Gov Cor hence my Correction is 66 links to West on each 40 Chain returned and made this correction, + went to NW Cor of Sec 10. found post + pits well defined from thence I run West.

West 00 40 40 00 Set temp Quarter post

" " " 80 00 " " Sec Cor

" " " 39 87 found Quarter post well defined having intersected the line 14 links North of Post

## A. J. Cochran Et. Al. Cont.

Since my correction is  $24\frac{1}{2}$  links on each 40 chains having made this correction I set permanent south East Cor of Sec 5 at the intersection of the two corrected lines Buried Basalt rock  $11 \times 20 \times 6$  marked # 1851 dug pits raised mound etc. Set permanent Quarter post on East line of Sec 8 in road at a point Equidistant from the S.E. + N.E. Sec Corners and set permanent Quarter post on East line of Sec 5 at a point 40 chains North of the S.E. Cor of Sec 5 and  $40 + 19\frac{1}{2}$  links South of N.E. Cor. Buried rocks marked # also Horse Shoe dug pits and raised mound. At request of John Adams I set Quarter post on South line of Sec 4 at a point on a true line Equidistant from the S.E. + S.W. Sec Corners. Buried Pieces of tin set post dug pits + raised mound.

To establish a post in the center of Sec 5 for the 4 Quarters I run from the Quarter Post on the North to Quarter Post on the South then from Quarter post on West to Quarter post on East, and set Cor at the intersection of the two corrected lines. Buried Basalt rock  $8 \times 8 \times 8$  set post raised mound dug pits + as per instructions

I hereby certify that the foregoing notes are true as they were taken on the 2, 4, + 5<sup>th</sup> days of March 1851

J. B. Raley  
Co Surveyor