

PLAT AND RECORD OF SURVEY No. 2719

Course	Degrees	Minutes	Chains	Links

ground mkd 4 notches on E and 2 notches on S. This cor is on W. hill side about 10 chs. E. of ravine, course N. W.

On returning to pt of commencing I find original Gov. cor. to secs 16-17-20-21, recified by A. M. Isaac, and which is decayed bits of old post in ground on gentle N.E. slope; old lines of ditch fencing run E. & N. from this cor. point, at which I set a basalt stone 15 x 11 x 7 ins. mkd. 4 notches on E. & 3 notches on S. (Nov. 14th 1887)

Jno. C. Arnold, County Surveyor

At proportionate distances and on true line, I set a basalt stone 17 x 8 x 5 1/2 ins. 12 ins in ground for cor. to secs. 8, 9, 16, 17 S. 37 N. R. 35 E. mkd. 4 notches on S. 1/4 E. about 300 lks west of a ravine, course N.E.

Jno. C. Arnold, County Surveyor

Corners set in a survey for Dr. S. Jones and Dr. A. P. Burg, Sep. 12 1857 Cor. for secs. 1, 2, 35th & 36th Tps. 3rd & 4th N. R. 30 E. which is the original post rotted off at ground and lying on a mound, in the center of which I find the lower end of said post, charred, and over which I set a stone 16 x 16 x 5 ins. mkd. 5 notches on W. and 1 notch on E.

This is sec. cor. bet. secs. 11th & 12th T. 3 N. R. 30 E. which is the lower charred end of original post, in center of plain old earth mound & pit on west, over which charred end of post, I set a stone 15 x 7 x 4 ins. mkd. 4 on W.

Cor. for secs. 34, 35th & 34 Tps. 3rd & 4th N. R. 30 E. which is the charred end of original post in old mound with top of original post lying by. I set over the charred end of post a stone 20 x 8 x 6 1/2 ins. (all under ground) Stone mkd. 3 notches on E. 1/4 W. & 3 notches on W. and 6 notches on N. School house in canon bet. N. 63° 30' E. about 20 chs. dist.

Cor. to secs. 11th & 12th T. 3 N. R. 30 E. which is a stone 13 x 7 x 6 ins. 12 ins. in ground, 5 notches on S. and 1 notch on E. - Deposit piece broken gut bottle (glass) Set as, per original notes

Cor. to secs. 7, 34th & 35th Tps. 3rd & 4th N. R. 30 E. which is a stone 21 x 10 x 6 ins. mkd. 6 notches on N. 1/4 & 2 notches on E. on west hill side, at original cor. pt. as per original notes - found old md. & pits.

Jno. C. Arnold, County Surveyor.