

Course
Degrees Minutes
Chains
Links

Corners set in locating center sec. 13. T. 3. N. R. 30 E., Request of Hamilton County, Nov. 22, 1888.

On to sec. 7, 12, 13 & 18, set over charred end of original post a stone 13x10x5 ins. 10 ins. in ground, mkd 6 notches on E and 4 notches on S.

The $\frac{1}{4}$ sec. cor. on N. bdy of said sec. 13, is a stone 18x5x5 ins. 16 ins. in ground, mkd $\frac{1}{4}$ on N., set at old cor. pt. mkd. by wagon box 48 ins. in ground, verified by A. W. Nyer, not present.

The $\frac{1}{4}$ sec. cor. on the W. bdy of said sec. 13, is a stone 16x10x6 ins. 14 ins. in ground, mkd $\frac{1}{4}$ on W., at pt. of true original $\frac{1}{4}$ sec. cor. verified by Geo. Reese, present, who marked the spot, when cor. was set.

The $\frac{1}{4}$ sec. cor. on S. bdy. of said sec. 13, was perpetuated by the said Geo. Reese, similarly, and at true cor. point, set a stone 16x8x5 ins. 14 ins. in ground, mkd. $\frac{1}{4}$ on N., old lines of fencing run N. & E.

The $\frac{1}{4}$ sec. cor. on E. bdy. of said sec. 13, is a stone 16x12x5 ins. 14 ins. in ground, mkd. $\frac{1}{4}$ on W. face, set on charred end of original post in ground 18 ins. at crossing of old fences N. & S. & E. & W.

Jno. C. Arnold, Co. Surveyor.

Corners set in the survey of C. A. Ross's add. to Centerville Feb. 14, 1889.

N. W. cor. sec. 19. T. 4 N. R. 35 E., which is a basalt stone 19x10x10 ins. 19 ins. in ground, mkd 6 notches on E and 3 notches on S. at pt. of original cor. verified by Wm. Villoughby and J. D. Stokes, both present, in road, course E⁹⁰ W., 133 ft. N. of house.

The $\frac{1}{4}$ sec. cor. on W. bdy. of sec. 19. T. 4 N. R. 35 E., which is a stone 14x12x7 ins. 14 ins. in ground in road, course E⁹⁰ W. Stone mkd $\frac{1}{4}$ on W. and set on true line midway between sec. corners.

Jno. C. Arnold, County Surveyor.