

## PLAT AND RECORD OF SURVEY No. 39 19

Request of Wm. Martin, Ireland heirs, et al. Mar. 5. 1889.

Subdivision of Sec 1 T. 57 N. R. 35 E. W. 7 M.

Peter Nichols and Jonathan Felbert, sworn, chainbearers; Geo. Ireland and E. C. Walker, sworn flagmen; Inset used, a mason Theodolite.

I commence at acknowledge cor. to secs. 1, 2, 11 & 12, T. 57 N. R. 35 E.

and run, on a random line bet. secs. 1 & 2.

North  
 1826 6 The Stone is sec. cor. on  $\frac{1}{2}$  of line bet. secs. 1 & 2 (See A. L. Coffey P. 71, 92)  
 2391 6 Strigating ditch, course N. W.  
 2664 6 The  $\frac{1}{4}$  sec. cor. bet. secs. 1 & 2, which is an old split for post, in a mound

of stone; I call E. D. Stillman, who appears and says, that he has a number of years ago, run the original box post, <sup>which</sup> stood at this, identical, place, and, for years, it stood here; that he has made use of this cor. in fencing, and identifies this, as the true cor. pt., from fences, run, E. W. & S.; that this cor. has not been questioned, to his knowledge, and that he has been acquainted with this cor. for, at least, 16 years.

I, therefore, accept this cor. as true, and with my inset, cor. and a foresight (magnetic course)  $71.21^{\circ} E$ , I run, on random line, from  $\frac{1}{4}$  sec.

North  
 1350 S. side of mill race.  
 1725 Center R. R. track, about  $N. 60^{\circ} E + S. 60^{\circ} W$ .  
 2206 S. edge of water. course, about E. W.

Mar. 5. 1889.

Ellis Ireland, sworn chmn, vice Peter Nichols.

East, on a random line, bet. secs. 1 & 12.

1320 N. E. cor. Pires and Elam's add. to Milton; Stone cor. <sup>(by myself)</sup> previously est.

2350 Little W. W. river, 16 ft. wide, runs nearly N. & S.

2498 A point 3 ft N. of low cottonwood, 8 ins. dia.,  $\frac{1}{2}$  way on N. near ground

2504 W. W. river 40 ft. wide runs about N. (W. side)

2524 " " " " " " " " " " " "

2644 " " " " " " " " " " " " (E side)

2640 Set temp. to S. cor, find no traces of original cor.

2920 A point, 8 ft. west of water's edge on W. side of Tom's land.

I turn Right,  $90^{\circ}$  and measure 100 ft., and mark pt. moving my instrument, and setting over the last named

Deeds Minutes Chains Links

points with a foresight on the R.A. point; Stum Right; 67° 28' to a flag on random sec. line, near summit of bluff on E. side of Simalium River, thus making dist. from R.A. pt. to flag 241 feet. ∴ 2920 + 241 = 3161

3161 Flag on random sec. line.  
 3981 Angle of road in lane South and East.  
 5305 Int. N. & S. line 3½ ft. S. of accepted stone cor. to sees. 1+12, on line bet ranges 35+36 E. - Cor. ratified by W. Pierce, of Milton-

I move temp. ¼ sec. cor., East 12½ ft., then North 1¾ feet, and set a smooth boulder, 22x13x8 ins. 18 ins. in ground for ¼ sec. cor. bet. sees. 1+12., mkd. ¼ on N. face, on a gravel bar, from which an alder, 5 ins. dia. bears S. 62° W. 16 feet dist.; a cottonwood 9 ins. dia. bears N. 22° 22' E. 99 ft. dist.

I move temp. ⅙ sec. cor. on W. ½ of line bet. sees. 1+12, East 6½ feet, then N. 7½ ft. and set a smooth, river boulder, 17x7x5 ins. 14 ins. in ground, mkd. + on top. Mar. 6 - '89.

North on a random line bet. ranges 35+36 E. ra. 21.306

Along traveled road in lanes, course N.  
 2640 Set temp. ¼ sec. cor.; find no traces of original ¼ sec. cor.  
 5310 To stone sec. cor. - Mr. <sup>Jas</sup> Patterson called; appears and says that this stone marks the true N.E. cor. of 25 N. R. 35 E.; that he has often seen the Gov. post here; has known this cor. for the last 26 years; that he identifies same, by lines of old fences runig. N. S. & E. from this cor.; that the ¼ sec. cor., on E. bndy. sec. 1, has been considered extinct; that he never saw it himself, nor heard any one else say it had ever been seen, although he had often hunted for it; Singsur of J. Tallat, & all present, but can ascertain nothing concerning locality of said orig. ¼ sec. cor.

I, therefore, move temp. ¼ sec. cor., on E. bndy. sec. 1, South, 15 feet, and set a porous basalt stone 18x12x9 ins. 16 ins. in ground for ¼ sec. cor., mkd. ¼ on W.

West, on rand Sp. line, N. bndy. sec. 1. 25 N. R. 35 E. ra. 21.306

88 20 2640 Set temp. ¼ sec.  
 2662 Int. N. & S. line 12 ins. S of stone ind., under N. & S. fence, claimed by Ira Berry, to mark true place of orig. ¼ sec. George

Acres	Degrees	Minutes	Chains	Links
-------	---------	---------	--------	-------

Bury having found the original  $\frac{1}{4}$  sec. cor. here.

West

- 2926 Old channel of branch of Sumatsum, course 71 W.
- 2430 Small " " " "
- 3262 Larger " " " "
- 3666 Main " " " " nearly N. & 82 ft. wide.
- 2000 Stone md., purporting to be  $\frac{1}{4}$  sec. cor. on W. of N. bdy. sec. 1.
- 5325 " " under N. & S. fence, marking location of original NW cor.

sec. 1. verified by Jonathan Talbot, chmn. — The point verified by Messrs. Ira and Geo Bury, being within 3 links of my measure, I, therefore, accept it. I call upon Wm. Saltat and my whole crew to notify all concerned parties that, tomorrow, I will set center sec. 1  $\frac{1}{4}$  S. 71. R. 35 E. — I'm puzd to notify Aaron Miller.

March 7<sup>th</sup> 1889.

From  $\frac{1}{4}$  sec. cor. on E. bdy. sec. 1, west on true center sec. line  
 5356 To  $\frac{1}{4}$  sec. cor. on West bdy. sec. 1. I then run from  $\frac{1}{4}$  sec. cor. on S. bdy. sec. 1, a true center sec. line to  $\frac{1}{4}$  sec. cor. on N. bdy. sec. 1. and find the point of intersection of these  $\frac{1}{2}$  sec. lines, to be 27066 feet E. of  $\frac{1}{4}$  sec. cor. on W. bdy., and 2665 feet N. of  $\frac{1}{4}$  sec. cor. on S. bdy. sec. 1.

No one appearing to oppose, at the point of intersection of the center sec. lines, as described, I set a smooth oval shaped boulder 15x14x7-24 ins in ground (to be below plowing) for center sec. 1  $\frac{1}{4}$  S. 71. R. 35 E. mkd. C 51 on North, and set post over it, in plowed field, 77 feet N. of E. & W. fence, and 93 ft E. of precipitous bluff, E. of Sumatsum.

March 8. 1889.

Wm. Martin's block. (Description)

Com. at center sec. 1, and run W. on center sec. line 440 yds; thence S. on line parallel to N. & S. center sec line, 275 yds; thence E., on line parallel to E. & W. center sec. line, 440 yds, to N. & S. center sec. line; thence N., on said N. & S. center sec. line, 275 yds., to pt. of coming — all in sec. 1  $\frac{1}{4}$  S. 71. R. 35 E.

George Shuland's block. (Description)

Com at S.E. cor. of Wm. Martin's lot, and run west, on line parallel to E. & W. center sec. line, and along S. bdy. of Wm. Martin's lot, to intersect line N. & S. through center of  $\frac{1}{4}$  sec. 1; thence S. on said N. & S. center line through  $\frac{1}{4}$  sec. 1, 385 yds; thence E., on line parallel, N. & S., through center sec. 1, to intersect

Acres  
Meters  
Chains  
Links

said N. & S. center sec. line; thence N. along said N. & S. center sec. l., a distance of 355 yds. to pt. of commencing, all in sec. 10 S. 5 N. R. 35 E.

Mrs. S. E. Ireland's lot. (Description)

All that part of E. ½ of S. W. ¼ of Sec. 1, T. 5 N. R. 35 E., lying South of George Ireland's lot, in said section.

Set a porous boulder, 24x12x4 ins., 22 ins. in ground, for cor. to Mr. Martin and Geo. Ireland, on N. & S. center sec. line, mkd. + N. face, at foot of bluff about 60 ft. high, on E. side of Timalum.

Set a smooth boulder, 30x8x7 ins., 18 ins. in ground, for cor. to Geo. Ireland, and Mrs. S. E. Ireland, mkd. + on top.

Set a smooth boulder 10x7x4 ins., 8 ins. in ground, for 76 sec. cor., on E. ½ of E. W. center sec. l., mkd. + on top, in plowed, on gentle N. slope.

Set a rough stone, 10x8x4 ins., 8 ins. in ground, for 76 sec. cor., on N. ½ of N. & S. center sec. l., mkd. + on N.

Set a smooth boulder, 14x10x5 ins., 12 ins. in ground, for 76 sec. cor., on W. ½ of E. & W. center sec. l., mkd. + on top, and raised a md. of stone on cor. 33 ¾ ft. E. of this 76 sec. cor., I drive post for N. W. cor. of Mrs. Martin's block, in west edge of small branch course N. W.

Set a smooth boulder, 18 ins. long by 8 ins. sq., 16 ins. in ground for N. W. cor. to Geo. Ireland's block, mkd. + on top, and raised a md. of stone on cor., from which a cottonwood tree 5 ins. dia., bears S. 50° W. 5 ft. dist.

For S. W. cor. of Mrs. Martin's block, I drive post 35 ¾ ft. E. of this 76 sec. cor.

Set cottonwood post 4 ins. dia., 4 ft. long, 18 ins. in ground, for S. W. cor. to Geo. Ireland's block, mkd. & T I on N. E. and S E I on S. S. This cor. is 7 ft. N. and 1 ft. E. of old cottonwood stump 18 ins. dia.

Mar. 8, 1889.

PLAT AND RECORD OF SURVEY No. 39

Course. Degree. Minutes. Chains. Links.

plat of Secs. 1, 2, 11 & 12 T. 5 N. R. 35 E. Will. Mer.

