



Acres, Min., Chas., Linc.

- From the 1/4 Sec ea bet Sec 1 & 12  
Thence west bet Secs 1 & 12  
Var 20° E
- 20 00 Set temporary 1/4 ea
- 40 46 Intersect 24 1/2 miles south of the ea to Secs 1-2-11 & 12  
S 89° 39' E on true line
- 20 25 Set Post for 1/4 ea
- 40 46 The 1/4 Sec ea  
Thence East bet Secs 1 & 12  
Var 20° E
- 20 00 Set temporary 1/4 ea
- 40 00 Set temporary 1/4 ea
- 69 35 Intersect catwalk 1/4 mile south of the corner Secs 6 & 7 T. 1 S. R. 36 E  
from which I run  
west on true line
- 49 02 Set Post for 1/4 ea  
Thence South bet Posts 2 & 3 Var 18° E
- 39 95 Intersect 55 1/2 miles west of the 1/4 ea corner  
Thence N 47° W on true line
- 19 27 1/2 Set Post for 1/4 ea
- 39 95 The 1/4 ea corner on N 8 1/4 Sec 12  
Thence North through center S 3 1/4 Sec 1  
Var 21° E
- 20 00 Set temporary 1/4 ea corner
- 40 00 Set temporary 1/4 ea corner  
Thence west Var 19° E
- 20 00 Set temporary 1/4 ea corner
- 40 00 Set temporary 1/4 ea corner for center Sec 1  
I then commenced at the 1/4 Sec ea bet Sec 1 & 12.  
Thence North through center Sec 1  
Var 21° E

PLAT AND RECORD OF SURVEY No. 69/29

Courses. Degrees. Minutes. Chains. Links.

- 20 50 set temporary 1/16 corner
- 40 00 a point 20 1/2 m South and 115 1/2 m west of temporary State Boundary
- 60 50 set temporary 1/16 corner
- 79 50 Intersect 318 1/2 m west of the 1/4 sec corner on N 1/2 Sec 1  
Thence S 2° 10' W on true line
- 39 75 set Post for 1/16 corner in center Sec 1
- 79 50 the 1/4 sec cor  
I have run East from center Sec 1
- 20 00 set Post for 1/16 cor
- 40 00 set Post for 1/16 cor  
Thence S. 38' W
- 20 00 set Post for 1/16 cor
- 40 00 the 1/16 corner on South half N 3/4 Sec 12

John W. Winchell

County Surveyor

Surveyed for John Rhodes in T 1 N 6 R 2 E Sec 6 1894

I commenced at the 1/4 sec cor bet Sec 12 & 14

Thence west on random line through center Sec 14 to 2130 1/2

33 40 the 1/4 sec cor

75 55 U. Reservation line N 58° W S 55° E

79 95 Intersect 1/4 sec cor bet Sec 14 & 15

I commenced at the 1/4 sec cor bet Sec 14 & 23

Thence north on random line through center Sec 14 to 5130 1/2

15 96 reservation line N 58° W

78 53 Intersect to 1/4 sec cor 15 1/2 m East of 1/4 sec cor bet Sec 11 & 14

Thence south on true line

40 07 set Stone 22 x 12 x 12 for center Sec 14

62 57 set Stone 15 x 55 for closing corner on U. Reservation line

Thence S 58° W 344 to 92 mile Stone S 58° E 500 then S 45° W 1575 then to remainder corner bet Sec 14 & 23 300 1/2 m East of 1/4 sec cor bet Sec 14 & 15

John W. Winchell County Surveyor