

PLAT AND RECORD OF SURVEY No. 79

Surveyed for J. F. Lee and His Heirs

Oct the 30<sup>th</sup> 1896

Course. Degrees. Minutes. Chains. Links.

L 2 N R 33 E

I commenced at the 1/16 corner  
in center of the 6 1/2 Sec 11

Hence I ran North on a  
Random line through the  
center of the N 6 1/4 Sec 11

Var 22° E

5 50 Rail Road course E 8 1/2 W

20 00 Set temporary 1/16 corner

20 25 left bank of Matilda creek west - 400 Mts wide Foreigners of land

24 00 North channel of river 300 Mts wide course W

39 97 Natural line between Sec 2 & 8 11 21 Mts East of the 1/16 cor-  
ner N 6 1/4 Sec 11 this corner being obliterated I

proceed to reestablish it - Spirit

I commence at the corner to Sec 1-2-11 & 12

which is a Stone in center of Stone

Hence I run west on random line to Sec 28 11

Var 20° E

20 50 Set temporary 1/16 cor

39 75 Subst 5 Mts north of the 1/16 cor

from which

a Cottonwood 16 ins dia to N 65° E 54 Mts dist

" 24 " " " South 35 " "

Hence N 89° 50' E on true line

19 87 Set Stone 12 x 6 x 6 in toward of Stone for 1/16 cor

39 75 the corner to Sec 1-2-11 & 12

Hence S 0 19' E on true line through center N 6 1/4 Sec 11

19 98

Var 20° E

19 98 Set Stone 10 x 6 x 6 for 1/16 cor in center N 3 1/4 Sec 11

39 97 the 1/16 cor in center S 1/2 Sec 11

J. H. Winchell County Surveyor