

# PLAT AND RECORD OF SURVEY No. 97

John Hager

March 2<sup>nd</sup> 1898

T 3 N R 32 E W M

Degrees Minutes Chains Links

3 I commenced at the corner Secs 16-17-28 & 29

these North bet Secs 16 & 17

Var  $21^{\circ} 30' E$

39 50 fence runs E - N & S

40 00 could find no  $\frac{1}{4}$  Sec cor set Temporary  $\frac{1}{4}$  Sec cor

79 60 the corner to Secs 8-9-16 & 17

these South on true line

39 80 set Stone for  $\frac{1}{4}$  Sec cor

from cor to Secs 8-9-16 & 17 run

East bet Secs 9 & 16 on random line

Var  $22^{\circ} E$

36 15 gulch runs SW

40 12 wire fence N & S could find no  $\frac{1}{4}$  Sec cor

61 25 gulch runs SW

80 30 the cor to Secs 15-16-17 & 10

these South bet Secs 15 & 16

40 00 set Temporary  $\frac{1}{4}$  Sec cor

44 50 gulch runs N

7943  $\frac{1}{2}$  3521

79 43 cor to Secs 15 & 16 - 21 & 2

these North on true line

39 21 set Stone for  $\frac{1}{4}$  Sec cor bet Secs 15 & 16

these I ran West through center Sec 16 and established a right line through center from  $\frac{1}{4}$  Sec cor to  $\frac{1}{4}$  Sec corner which was the best survey John W. Timbrell county surveyor