

City of Echo July 27 on Joe Leesen ang 15⁰⁰ T. 3 N. R. 29

Degrees Minutes Chains Links

Arthur Hammer chairman
 J. P. Nelson "
 Joel Kallstead flagman

From corner to Secs. 9, 10, 15⁰⁰ and 16 T. 3 N. R. 29
 E. W. Co.

Thence I run West on true line
 40 73 to 1/4 Sec. cor. between Secs. 9 and 16

Thence I run West on random line
 40 00 set ten Sec. cor.

121 80 intersect 44 lks S. of Sec. cor.

East

81 20 set ^{ten} Sec. cor at proportional distance
 From 1/4 Sec. cor. between Secs. 8⁰⁰ and 9

Thence South on random line
 40 00 set ten Sec. cor. on line just previously
 established

80 00 set ten 1/4 Sec. cor.

120 00 set ten Sec. cor.

200 80 intersect 86 lks. E. of Sec. cor. where I found
 old stake and by digging found rotted point
 of old stake.

North

80 48 set stake on E. and W. line

120 72 set at proportional distance

160 97 set Sec. cor. for Secs. 8, 9, 10⁰⁰ and 17 on N⁰⁰ and S.

line just previously established.

Course.	Degrees. Minutes.	Chains.	Links.	
				West on random line between Secs. 16 and 21
40	00			set ten 1/4 Sec. cor.
80	50			intersect 18 lks. S. of stake on E. 2 nd W. line
162	34			intersect 46 lks. S. of Sec. cor.
				East on true line
81	17			set corner for Secs. 16, 17, 20 nd / 21 on E. 2 nd W. line previously established.
				Thence S. 0° 8' E.
40	58 1/2			set stake for 1/4 Sec. cor.
				North 0° 28' E. on true line between Secs. 16 & 21
40	24			set rock for 1/4 Sec. cor. between Secs. 16 & 17
				South on random line between Secs. 15 & 16
40	00			set ten 1/4 Sec. cor.
79	94			to corner for Secs. 15, 16, 21 st / 22
				N. on true line
39	79			Set 1/4 Sec. cor. between Secs. 15 th and 16.
				West on random line through center of Sec. 16.
40	00			set ten 1/4 Sec. cor.
80	08			intersect 34 lks. N. of 1/4 Sec. cor.
				North on true line through center of Sec. 16.
				The 1/4 Sec. cor. on N. side of Sec. being on right
40	10			intersect E. 2 nd W. line just previously established where I drive a nail in porch of a dwelling house belonging to Mr. Kallstead. Said nail being 4 1/2 ft. N. and 9 ft. east of the N. W. corner of said house. Said center of Sec. 16 being 13 3/4 ft. West and 46 ft. S. of N. E. corner of City Block.
				Continuation of Survey for City of Cole
				Aug. 16 '04. Arthur Hammer 2 nd Bert Campbell chain
				and Joel Kallstead flagman.

From	Wells	Chains	Links
------	-------	--------	-------

From center of Sec. 16 T. 3 N. R. 29 E. N. Co.
 Thence I run East through center of E. 1/2 of Sec. 16
 on true line the 1/4 Sec. cor on E. being in sight

20 00

set ten 1/6 Sec. cor.

40 34

to 1/4 Sec. cor.

West

20 17

set rock for 1/6 Sec. cor.

From 1/4 Sec. cor. between Secs. 16^{2nd} & 21

Thence I run East on random line

20 00

set ten 1/6 Sec. cor.

40 57

to Sec. cor.

West on true line

20 28 1/2

set granite rock for 1/6 Sec. cor.

Continue the survey for Joe Leezer

From the center of Sec. 16 T. 3 N. R. 29 E. N. Co.

Thence I run South on random line

20 00

set ten 1/6 Sec. cor.

40 04

intersect 42 lks. S. 1/4 Sec. cor.

North 0° 36' E. on true line

20 02

set stake for 1/6 Sec. cor.

From the corner to Secs. 8, 9, 16^{2nd} & 17

Thence I run N. on random line between Secs. 16^{2nd} & 17

20 00

set ten 1/6 Sec. cor.

40 21

intersect 14 lks E. of 1/4 Sec. cor.

South 0° 12' E. on true line

20 10 1/2

set Stone for 1/6 Sec. cor.

J. H. Kimbrell Co Surveyor
 by Gray Kimbrell Deputy