

Links

For Robert Stanfield July 10<sup>th</sup> '05  
 Secs. 31<sup>st</sup> & 32<sup>nd</sup> T. 4 N. & Secs. 5<sup>th</sup> & 7<sup>th</sup> R. 29 E. & 2<sup>nd</sup> R.

From the corners of Townships 3<sup>rd</sup> & 4<sup>th</sup> N.  
 and Ranges 28<sup>th</sup> & 29<sup>th</sup> E. T. Co.

Thence I run N. in random line

40 00 set tem. 1/4 Sec. cor.

80 00 set tem. Sec. cor.

319 72 intersect 132 lks. E. of corner to Secs. 12<sup>th</sup> & 13<sup>th</sup>  
 R. 28 E. and Secs. 7<sup>th</sup> & 18 R. 29 E.

South 0° 14' E. on true line

239 79 set rock for corner to Secs. 25<sup>th</sup> & 31 R. 28 E.  
 and Secs. 30<sup>th</sup> & 31 R. 29 E.

279 75 1/2 set 1/4 Sec. cor between Sec 36 R. 28<sup>th</sup> and Sec. 31  
 R. 29 E.

East on random line between Secs 30<sup>th</sup> & 31.

48 50 set tem. 1/4 Sec. cor.

68 50 set tem. 1/6 Sec. cor.

88 50 set tem. Sec. cor.

108 51 set tem. 1/6 Sec. cor.

128 52 1/2 set tem. 1/4 Sec. cor.

168 55 set tem. Sec. cor.

329 32 intersect old plowed furrow which was  
 evidently plowed along section line running N. & S.

Course.	Degree	Minutes	Chains	Links
---------	--------	---------	--------	-------

- which we accepted as the true line  
 Thence running west I set each ten corner  
 at their proper proportional distances  
 North on random line between Secs. 31 & 32
- 40 00 set ten 1/4 Sec. cor.  
 60 00 set ten 1/4 Sec. cor.  
 80 00 set ten Sec. cor. 1/2 the distance W. of stake previously  
 set for N. and S. line
- 160 60 intersect 9 lks. W. of Sec. cor. where by digging  
 I found rotted point of old stake in ground and  
 a piece of old stake lying near by.
- Thence South on true line and on  
 N. and S. line previously established
- 80 30 I set a rock 10" x 10" x 20" for corner to Secs.  
 29, 30, 31 and 32
- Thence South 0° 5' W. on true line
- 20 09 1/2 set rock 4" x 14" x 18" for 1/4 Sec. cor.  
 40 15 set rock 8" x 10" x 18" for 1/4 Sec. cor.  
 South 89° 48' W. on true line between  
 Secs. 30 and 31
- 20 12' set rock 6" x 10" x 14" for 1/4 Sec. cor.  
 40 24' set stake for 1/4 Sec. cor.
- East on random line between Secs.  
 5 T. 3 N. and Sec. 32 T 4 N.
- 40 00 set ten 1/4 Sec. cor.  
 80 00 set ten Sec. cor.
- 159 02 intersect 58 lks. N. of corner to Secs. 32 and 34  
 T. 3 N. and Secs. 33 and 34 T 4 N.
- North 89° 48' W. on true line
- 79 51 set rock for corner of Secs. 4, 5 and 5 T. 3 N. and  
 Secs. 32 and 33 T 4 N.

Chains Links

39 75½ set rock for 14 Sec. Cor. between Secs. 5 & 31  
and Secs. 32 & 4 N.

From 14 Sec. Cor. between Secs. 32 and 33 where  
I found an old ditch fence running N. and S.  
This I accepted as the true corner and set rock

Thence N. on random line

40 00 set tem. Sec. Cor. on N. 2d S. line previously  
established and 80 lks. of stake previously set

79 82 to Sec. Cor. where I found well preserved old stake  
and after digging in immediate vicinity found  
place where the point of old stake had rotted  
off in the ground.

Thence South

39 91 I set rock 8" x 10" x 18" on N. and S. line  
previously established

South 89° 84' W. on true line between Secs.  
29 2d & 32

40 29 set stake for 14 Sec. Cor.

60 40½ set stake for 16 Sec. Cor.

West on random line through center of Sec. 31

20 00 set tem. 16 Sec. Cor.

40 00 set tem. 14 Sec. Cor.

89 90 intersect 14 lks. S. of 16 Sec. Cor.

South on random line through center  
of Sec. 31

40 10 intersect true E. 2d W. line 22 lks. W. of  
tem stake.

80 04 set rock 4" x 13" x 15" for 14 Sec. Cor. in center  
of Sec. 31

Thence South 0° 6' E. on true line through  
E. ½ of Sec. 31

20 03 set stake for 16 Sec. Cor.

PLAT AND RECORD OF SURVEY No.

Course.	Degrees. Minutes.	Chains.	Links.	
				South on random line through center of N. E. 1/4 of Sec. 31
20	00			set tem. 1/6 Sec. Cor.
40	20			intersect 15 lks. W. of 1/6 Sec. Cor.
				North $0^{\circ}13'$ W. on true line
20	07 1/2			set rock $8" \times 14" \times 18"$ in center of N. W. 1/4 of Sec. 31
				South on random line through the center of Sec. 32
40	00			set tem 1/6 Sec. Cor.
80	40			intersect 20 lks E. of 1/6 Sec. Cor.
				West on random line through the center of Sec. 32.
40	12			intersect true N. and S. line 42 lks. S. of tem stake.
60	00			set tem 1/6 Sec. Cor.
80	10			intersect 48 lks S. of 1/6 Sec. Cor.
				South $89^{\circ}40'$ W. on true line
19	99			set tem 1/6 Sec. Cor.
39	98			set 1/6 Sec. Cor. in center of Sec. 32 on N. and S. line previously established.
				South on random line through center of N. W. 1/4 of Sec. 32
20	00			set tem, 1/6 Sec. Cor.
40	16			intersect 8 lks. W. of 1/6 Sec. Cor.
				North $0^{\circ}7'$ W. on true line
20	08			set rock $5" \times 11" \times 16"$ for 1/6 Sec. Cor. in the center of the N. W. 1/4 of Sec. 32.
				South on random line through the center of Sec. 5 - T. 3 N. R. 29 E. W. Cor.
40	00			set tem 1/6 Sec. Cor.
80	08			intersect 68 lks W. of 1/6 Sec. Cor.

North  $0^{\circ} 28'$  W. to intersection with  
N.E. line of County Road running on  
N.E. side of O.R. & N. railroad right  
of way, where I set a rock for extreme  
southern point of land belonging Robert Stanford  
J. W. Kimbell Co. Surveyors.  
by Gary Kimbell Deputy.