

Surveyed for J.A. McWorter Apr. the 14th 1890

By J.W. Kimbrell County Surveyor plat No 107

I commenced at the corner J 38 16 38 E W M to Sec 5-6-7 & 8

Thence East bet Sec 5 & 8
Var 20° 8

on Offset of 100 lks south
18 00 set back north 100 lks on line

39 52 set temporary 1/4 Sec corner

59 28 " " 1/16 corner

79 05 could find no Sec corner to Sec 4-5-8 & 9 and set temporary corner
Thence East bet Sec 4 & 9
Var 20° 8

19 85 set temporary 1/16 corner

39 90 set temporary 1/4 Sec corner

59 85 set temporary 1/16 corner

79 80 could find no Sec corner to Sec 3-4-9 & 10 and set temporary Sec. corner
Thence East bet Sec 3 & 10
Var 20° 8

79 36 could find no corner to Sec 2-3-10 & 11 but at 130 lks further East find the original corner to Sec 2-3-10 & 11
Making an excess of 130 lks in the 3 miles run I therefore run west allowing 43 1/2 lks of an excess to each mile over the U.S. field notes and at

79 79 1/2 set post for corner to Sec 3-4-9 & 10
Thence on line

40 06 set stone 20x9x6 for 1/4 Sec corner bet Sec 4 & 9

40 12 set stone 18x8x7 for 1/16 corner



80 24 set stone 21x13x6 for corner to Sec 4-5-8 & 9
Thence West bet Sec 5 & 8

19 81 set stone 13x7x4 for 1/16 corner

39 63 1/2 set stone 17x12x7 inches for 1/4 Sec corner bet Sec 5-8 & 8

79 27 the corner to Sec 5-6-7 & 8
I commence at the corner to Sec 4-5-8 & 9
Thence North bet Sec 4 & 5
Var 20° 15' E

26 00 Rail Road course N 58° 35' E

40 00 could find no 1/4 Sec corner set temporary corner

79 60 set temporary corner for 4 & 5
commencing at the 1/4 Sec corner bet Sec 4 & 9
Thence North through center Sec 4
Var 20° 8

20 00 set temporary 1/16 corner for center 8 1/2 Sec 4

40 00 set temporary 1/16 corner for center Sec 4

54 00 through 305 lks wide course East

60 00 set temporary 1/16 corner for center N 1/2 Sec 4

60 40 through 456 lks across course East

79 79 I intersect North Side 12 lks West of the 1/4 Sec corner
The course of this line would be S 1/2 W
commenced at the 1/4 Sec corner bet Sec 4 & 5
Thence East through center Sec 4
Var 20° 8

20 00 set temporary 1/16 corner for center W 1/2 Sec 4

79 80 I intersect True N & S line 30 lks North of 1st stake
for center on line previously run

60 00 set temporary 1/16 corner for center E 1/2 Sec 4

79 56 I intersect 27 lks North of the 1/4 Sec corner bet Sec 3 & 4
Thence N 89° 36' W on True line

19 85 set 1/16 corner for center E 1/2 Sec 4

39 70 set 1/16 corner for center Sec 4

59 62 set 1/16 corner for center W 1/2 Sec 4

79 56 the 1/4 Sec corner bet Sec 4 & 5

