

I commenced at the corner to Sec 1-2-11 & 12
thence East bet Sec 1 & 12
Var 20° E

20 00 set Stone for 1/16 corner for South Boundary S 8 1/4
thence South set Stone for 1/16 corner for East Boundary
I commenced at the corner to Sec 1-2-11 & 12
thence South bet Sec 11 & 12
Var 20° E

20 00 set temporary 1/16 corner
40 20 intersect 50 lbs west of the 1/4 Sec corner bet Sec 11 & 12
from which I run N 40° W on true line

20 10 set Stone in Mid. of Stone for 1/16 corner
40 20 the corner to Sec 1-2-11 & 12 J.W. Kimball county surveyor

Survey completed July the 26th 1891

I commenced at the 1/4 Sec corner bet Sec 34 & 35 -
thence North bet Sec 34 & 35 -
Var 21° 30' E

9 00 Rock cliff 10 feet high course NW 1/4 S E
13 55 Rocky cliff 15 feet high descend.

20 00 set Stone in Mid. of Stone for 1/16 corner
40 00 the corner to Sec 26-27-34 & 35 -
I commenced at the 1/4 Sec corner bet Sec 27 & 34
which is original Post in Mid. of Stone
from which
a Spruce Bear S 41° W 1400 lbs dist -
from this corner I run East bet Sec 27 & 34

18 85 top of bluff 40 feet high N 1/4 S descend
20 00 set Stone in Mid. of Stone for 1/16 corner
40 00 the corner to Sec 26-27-34 & 35 -
from which I run West
20 00 to 1/16 corner on N Side NE 1/4 Sec 34
thence South through NE 1/4 Sec 34

6 50 top of high ridge S W 1/4 S E
20 00 set Stone for 1/16 corner in center N E 1/4 Sec 34
J.W. Kimball Private Surveyor

Surveyed for Oliver Perino M. Johnson & Parker June 20th 1890
by J.W. Kimball county Surveyor Plat No. 115

I commenced at the 1/4 Sec corner bet Sec 5 & 6
thence East through center Sec 5
Var 20° E

15 00 Var 18° E
18 00 Var 22° 30' E
20 00 set temporary 1/16 corner
Var 22° E

24 00 var 19° 15' E
25 50 var 17° 15' E
30 30 fence S 1° 28' E
top of hill

31 00 descend very steep hillside
40 00 set temporary 1/16 corner
80 40 intersect 55 lbs south
of the 1/4 Sec corner
bet Sec 4 & 5
thence S 89° 45' W on true line

40 57 true center Sec 5
from which I mark -
a Pine 3 ins dia bet S 61° E 1 1/2 lbs dist
80 40 the 1/4 Sec corner bet Sec 5 & 6
I commenced at the 1/4 Sec corner bet Sec 5 & 6
~~thence North through center Sec 5~~
from which
a Pine 5 ins dia bet S 8 1/2° E 38 lbs dist
a Pine 5 " " " N 4° W 33 " "
thence I run North through center Sec 5
Var 20° E

20 00 set temporary 1/16 corner
39 45 intersect 17 lbs west of first stake set on E & W line
80 22 intersect at the 1/4 Sec corner bet Sec 5 & 6
thence South on line through center Sec 5 -
19 34 set Post for 1/16 corner for center N side Sec 6 -
from which
a Pine 8 ins dia bet N 89° W 28 lbs dist;



4077 The 1/16 corner in cut Sec 5 as described above on S 1/4 W line
 a Post from which
 a Pine 3 ins dia to S 61° 8 1/2 lks dist-

6050 Set Post for 1/16 corner for cut S 1/2 Sec 5
 from which I mark
 a Pine 3 ins dia to N 65° W 17 lks dist-

8022 The 1/4 Sec corner to Sec 5 & 8
 I commenced at the 1/4 Sec corner to Sec 5 & 6
 thence South to Sec 5 & 8
 Var 20° E

2000 Set temporary 1/16 corner
 3978 Intersect 78 lks East of the corner to Sec 5-6-7 & 8
 from which
 a Sawrash 12 ins dia to S 48° 8 25 lks dist.
 " 12 " " " S 22° W 6 " "
 " 14 " " " N 63° W 48 " "
 a Pine 12 " " " N 40° E 60 " "
 thence North 107' E on true line

1989 Set Post for 1/16 corner
 7978 The 1/4 Sec corner to Sec 5 & 6
 I commenced at the corner to Sec 1-6-7 & 12
 on Guide Meridian to S 18 1/2 39 & 40 E
 from which
 a Pine 30 ins dia to S 20° E 274 lks dist
 a " 40 " " " S 42° W 427 " "
 Var 1° E
 thence North to Sec 1 & 6
 Var 21° 15' E

2000 Set temporary 1/16 corner
 4030 Intersect 38 lks West of the 1/4 Sec corner to Sec 1 & 6
 from which
 a Pine 30 ins dia to N 87° W 149 lks dist-
 " 20 " " " S 25° W 127 " "
 So 33' W on true line

2016 Set Post for 1/16 corner
 4030 The corner to Sec 6-7-1 & 12

Post secured
 I Re-established set Stone 20 x 5 x 5

I commenced at the corner to Sec 5-6-7 & 8
 thence South to Sec 7 & 8 on random line
 var 20° E

2000 Set temporary 1/16 corner
 4050 I intersect 166 lks West of the 1/4 Sec corner to Sec 7 & 8
 thence True N 2° 22' W on true line

2025 Set Post for 1/16 corner
 4050 The corner to Sec 5-6-7 & 8
 I then commenced at the 1/4 Sec corner to Sec 7 & 8
 and ran South to Sec 7 & 8
 Var 29° E

700 Var 28° 30' E
 1200 Road S of W
 1591 Top of cliff S of W
 3911 Intersect 170 lks West of the corner to Sec 7-8-17 & 18
 thence True N 2° 40' W on true line

1955 Set Stone for 1/16 corner in end of Stone
 3911 The 1/4 Sec corner to Sec 7 & 8
 J.W. Trimball
 County Surveyor

Surveyed for Wm B. Brothie June 25th 1890
 by J.W. Trimball County Surveyor Plat No 116

I commenced at the corner to Sec 5
 20-21-28 & 29 which is a Stone corner.
 reset by myself as county Surveyor on
 March the 29 1889 see Page 81 this book
 thence True East to Sec 21 & 28
 on random line Var 20° 15' E

Sec 20	Sec 21
Sec 29	Sec 28

1850 Spring branch runs S.W.
 2000 Set temporary 1/16 corner
 4000 found low 1/4 Sec corner at Spring 1/2, Exposed East
 8068 Intersect 18 lks South of the corner to Sec 21-22-27 & 28
 thence True S 89° 52' W on true line

4034 Set Post in Stone mound for 1/4 Sec corner to Sec 21 & 28
 6051 Set Post for 1/16 corner
 8068 The corner to Sec 20-21-28 & 29
 J.W. Trimball County Surveyor