

66 Surveyed for Robt Young & Son, Dec The 9 1886

By J.W. Kimbrell County Surveyor Plat No 58


I Commenced at the N.E. Corner Sec 19
 Hence East 4065 chains the $\frac{1}{4}$ Sec
 corner on North Side Sec 19 from
 which I run West 2000 chs and
 set Post in mound of Stone to
 the $\frac{1}{4}$ Sec corner
 The $\frac{1}{4}$ Sec corner on North Side Sec
 19 Hence South through Center Sec 19
 8340 chains the $\frac{1}{4}$ Sec corner on South
 Side Sec 19 I then started at the
 $\frac{1}{4}$ Sec corner on West Side Sec 19
 and run East through Center Sec 19
 3979 chains the Center Sec 19
 7979 " East boundary Sec 19
 but found no corner and set a Stake for Initial $\frac{1}{4}$ Sec
 corner from which a line 20 in bears S 2 feet and East 19 feet
 the $\frac{1}{4}$ Sec corner on West Side Sec 19 Hence East 1988 chains
 set Post Hence North 1985 chains set Post in mound
 of Stone to Center N.W. $\frac{1}{4}$ Sec 19 Hence North 3970 $\frac{1}{4}$ corner
 J.W. Kimbrell County Surveyor



Surveyed for Isaac Williamson Dec 10 1886

By J.W. Kimbrell County Surveyor Plat No. 59

I Commenced at the $\frac{1}{4}$ Sec corner on West Side Sec
 24 Hence North on 20° 4075 chains
 the N.W. corner Sec 24 from which I run
 South 2037 chains set Post from which a
 line 12 inch bears N 77° 104 links dist - a
 line 14 " " N 63° W 72 " " "
 the corner to Sec 13 = 14 = 238 24 from which
 a line 23 in bears N 44° W 25 links dist -
 a " 20 " " N 77° 161 " "
 a " 32 " " S 71° 148 " "
 Hence East 4062 chains $\frac{1}{4}$ Sec corner on North Side
 Sec 24 from which I run West 2031 chains set Post in mound of Stone
 from which a line 8 in bears S 53° 30' W 172 links distant Hence
 South 4037 chains the $\frac{1}{16}$ corner from which I
 run North 2018 chains and set Post for center N.W.
 $\frac{1}{4}$ Sec 24 from which a line 24 inch bears S 38° W 4 links
 a line 10 inch bears N 68° 38 links distant Hence West
 2035 chains the $\frac{1}{4}$ corner J.W. Kimbrell County Surveyor



Surveyed for Mrs E.C. Endroppe & S.F. Ferguson Dec. 10 1886

By J.W. Kimbrell County Surveyor Plat No 60

I Commenced at the $\frac{1}{4}$ Sec corner
 on North Side Sec 13 Hence West
 4108 chains to corner Sec 11 = 12 = 138 14
 from which a line 18 inch bears N 61° E
 45 links a line 18 " " N 78° W
 58 " a line 15 in bears S 55° W
 18 " a line 20 inch " S 25° E 79 links
 from which I run East 2054 chains
 set Post for $\frac{1}{4}$ corner in mound of Stone
 the N.W. corner Sec 13 Hence South
 4110 chains the $\frac{1}{4}$ Sec corner on West
 Side Sec 13 from which I run
 North 2055 chains set Post for $\frac{1}{8}$
 corner in mound of Stone
 the $\frac{1}{4}$ Sec corner on West Side
 Sec 13 Hence South 4107 chains
 the S.W. corner Sec 13 I then started at $\frac{1}{4}$ Sec corner on West
 Side Sec 13 Hence East through Center Sec 13 8091 chains
 the East boundary Sec 13 46 links South of $\frac{1}{4}$ Sec corner
 Hence South 4220 chains the S.E. corner Sec 13
 the $\frac{1}{8}$ corner on N Side N.E. $\frac{1}{4}$ Sec 24 Hence South 3948 chains
 the $\frac{1}{16}$ corner in center E $\frac{1}{2}$ Sec 24 from which I run
 North 1974 chains set Post in mound of Stone to center
 N.E. $\frac{1}{4}$ Sec 24 Hence West 4074 chains the $\frac{1}{16}$ corner
 in center N.W. $\frac{1}{4}$ Sec 24 from which I run East and
 at 2032 chains set Post for $\frac{1}{16}$ corner in center N.E. Sec 24
 from which a line 7 in ch Diagonals bears N 59° 30' W 52 links
 See Plat on page 63
 the $\frac{1}{4}$ Sec corner on South Side Sec 13 Hence North
 through Center Sec 13 8288 chains the $\frac{1}{4}$ Sec corner on
 North Side Sec 13 from which I run South 2057 chains set
 Post for center N.E. Sec 13 4115 chains the center Sec 13
 from which a line 25 inch bears S 29° E 212 links distant
 a line 28 inch bears S 31° W 261 links distant Hence South
 2056 chains set Post for $\frac{1}{16}$ corner in center S $\frac{1}{2}$ Sec 13 from
 which a line 14 in bears S 44° E 67 links distant a line 14 inch
 bears N 67° W 84 links dist - a line 24 inch bears N 23° W 330 links
 the center Sec 13 Hence West 2041 chains set Post for center
 N.W. Sec 13 from which a line 12 inch bears S 79° E 154 links
 a line 12 inch bears N 62° W 83 links distant
 Hence North 4100 the $\frac{1}{8}$ corner on North Side N.W. $\frac{1}{4}$ from which
 I run South 2060 chains set Post for $\frac{1}{16}$ corner
 Hence South 4131 chains $\frac{1}{8}$ corner on South Side S.W. $\frac{1}{4}$ from which
 I run North 2065 chains set Post in mound of Stone from which
 a line 18 inch bears S 47° E 337 links distant (over)

