

By order of H. W. Winn

May 25th 1905 20455 N 2345

Chains Links

- Commencing at the cor to sec 3-4-33 and 34 T 38 N R 346
 thence south bet sec 3 & 4
- 80 20 the cor to sec 3-4-9 & 10
 thence north on true line bet sec 3 & 4
- 40 10 set stone 16x10x8 inch for $\frac{1}{4}$ sec cor bet sec 3 & 4 marked $\frac{1}{4}$ on S face
- 60 15 set 2x2 strap iron $\frac{1}{2}$ x3 inch 24 inches long for $\frac{1}{16}$ cor
- 80 20 the cor to sec 3-4-33 & 34
 thence west bet sec 4 & 33
- 79 50 the cor to sec 4-5-32 & 33
 thence east on true line bet sec 4 & 33
- 39 75 set stone 14x8x3 inches marked $\frac{1}{4}$ on S face for $\frac{1}{4}$ sec cor bet sec 4 & 33
 thence south through center sec 4
- 79 91 to $\frac{1}{4}$ sec cor bet sec 4 & 9
 thence north on true line through center sec 4
- 59 94 set Iron Bolt 22x1 inches for $\frac{1}{16}$ cor in center N.E. sec 4

John W. Winchell County Surveyor

assisted by Geo Bentley and M. C. Mackintosh as charrman
 and John Seiss as flagman