

RECORD OF SURVEY No. 248

By Request of James W Foster Oct 3rd 1906

Chains Links

Sec. 36, T. 6, N. R. 27, E

1/4 Sec 36	1/4 Sec 36	1/4 Sec 36	1/4 Sec 36
Wm Davis	A. McHenry	W Ferguson	
1/4 Sec 36	1/4 Sec 36	1/4 Sec 36	1/4 Sec 36
J W Foster	Caplan	Br 2	
1/4 Sec 36	1/4 Sec 36	1/4 Sec 36	1/4 Sec 36

Commencing at the 1/4 sec cor bet Secs 35 & 36

thence South bet Secs 35 & 36

4190 a point - 30 lbs or of the cor to Secs 1-2-35-36 on the line

3 witness trees and post decayed I reestablished set New post from which

Old Henry tree Sawtooth 15 in chain bears S53°W 32 lbs dist

New " " " 4 " " " N74°W 22 " "

" " " Fir 3 " " " N72°E 15 " "

" " " Sawtooth 5 " " " S21°E 16 " "

thence North on true line bet Secs 35 & 36

2095 set post and deposite broken bottle from which

a fir 20 in chain bears west 106 lbs dist -

" " 22 " " " S50°E 25 " "

East on South boundary sec 36

4072 a point - 66 lbs north of 1/4 sec cor

thence west on true line

2036 set post and deposite broken bottle from which

a Womel 14 in chain bears S87°E 20 lbs dist -

" 12 " " " N 77°W 31 " "

North through center sec 36

2000 set Tempary 1/4 cor

4000 " " center sec 36

8231 a point - 200 lbs west of 1/4 sec cor bet Secs 25 & 36

East through center sec 36

2000 set Tempary 1/4 cor

4000 " " center sec 36

8379 a point - 118 lbs north of 1/4 sec cor

Chains Links

- Thence $N 52^{\circ} 01' W$ on same line through center sec 36
- 4034 1st post for center sec 36 from which
a fir 6 ins diam bears $N 40^{\circ} 06' 19$ lbs dist -
a fir 8 " " " $N 58^{\circ} W 16$ " "
- 6206 1st post for $\frac{1}{4}$ acre in center $W \frac{1}{2}$ sec 36 from which
a fir 5 ins diam bears North 1 lbs dist -
a fir 24 " " " South 15 lbs "
- 8379 the $\frac{1}{4}$ ac cor bet sec 35 & 36
From center sec 36 I ran $N 13^{\circ} W$ on same line
- 2043 1st post for $\frac{1}{4}$ acre in center $S \frac{1}{2}$ sec 36 from which
a fir 8 ins diam bears North 7 lbs dist -
a fir 3 " " " $S 70^{\circ} E 14$ " "
Thence west through $S W \frac{1}{4}$ sec 36
- 2000 2nd survey $\frac{1}{4}$ ac
- 4174 the $\frac{1}{4}$ acre on W by $S W \frac{1}{4}$ sec 36
Thence East on same line
- 2097 1st post for center $S W \frac{1}{4}$ sec 36 from which
a fir 6 ins diam bears $N 10^{\circ} W 8$ lbs dist -
a fir 10 " " " $S 12^{\circ} W 6$ " "

John Whimbale County Surveyor
Assisted by A. L. McFarlane and Hans Ross Chammion
and W. L. Alexon and Wm Doris Hagman & others