

by request of W.H. Daugherty Manager for the Umatilla Branch April 17th 1907

T 3 84 N 16° 28' 22.9"

Chains Links

Commencing at corner of Op° 3 84 N 16° 28' 22.9" 1 run
west on South Body Sec 36 on blank line sitting Sanjourng corners at 40 540 chs
and at 4 miles 2 chains and 16 lks intersect 140 lks South of cor to Sec 4-5-32 833
thence 1 run S 89° 46' E on same line and at

120 82 set Stone 10 + 9 + 8 for 1/4 Sec corner on South Body Sec 34

thence East to Sec 3 834

40 27 set Stone & Stake for corner to Sec 2-3-34 835-

thence East to Sec 2 835-

20 18 1/2 set post for 1/16 cor

40 27 set Stone & Post for 1/4 Sec cor and iron pipe 2" + 3" long

60 40 1/2 set post for 1/16 cor

80 54 set 3 iron pipe 2" + 3" long and post for cor to Sec 1-2-35 836

thence S 89° 46' E on S Body No 36 & N Body No 1

20 18 1/2 set post for 1/16 cor

40 27 " post and Stone for 1/4 Sec cor

60 40 1/2 " " " for 1/16 corner

80 54 the cor to Sec 1-6-31 836 and Op° 3 84 N 16° 28' 22.9"

North on Range line to Sec 31 836

47 58 ~~Umatilla~~ ^{through} across course west -

58 65 Umatilla near 22 lks across runs west -

75 61 O R 8 N 16 6 8 W

77 58 a point 14 lks west of center Sec 30-31-25 836

South on same line 1997 + 1997 + 1997 + 1997 = 7988 to 210 cor

Chains Links

- From the $\frac{1}{4}$ sec on lot nos 6 & 31 on Sjo me bet Sjo 314 N θ 296 yds
West bet nos 6 & 31
- 20 11 The $\frac{1}{16}$ corner
- 22 04 Fractional corner on N Bay NW $\frac{1}{4}$ sec 6
- 48 23 The corner to nos 1-6-31 & 36 a d en Sjo 314 N θ 25 & 296
- North bet nos 34 & 35-
- 40 00 1st temporary $\frac{1}{4}$ sec cor
- 60 00 " " $\frac{1}{16}$ cor
- 64 30 left bank of Umatilla river 200 lbs across
- 66 30 right bank " " runs west-
- 80 25 the cor to nos 26-27-34 & 35- from which I mark
a Balon 3 inch diam bears N47°W 25 " "
a Balon 5 " " " N18°E 25 " "
a Balon 12 " " " S76°E 26 " "
a Balon 8 " " " S39°W 58 " "
- thence west bet nos 27 & 34
- 40 20 the $\frac{1}{4}$ sec cor bet nos 27 & 34
East bet nos 26 & 35 ✓
- 79 82 a point 92 lbs South of witness cor to nos 25-26-35 & 36 a 95 lbs N 17 Sme cor point
set on same line 3991 sur post and then for $\frac{1}{4}$ sec cor
North bet nos 25 & 30
- 850 U.S. Navigation Fleet Canal runs west-
- 39 94 the $\frac{1}{4}$ sec cor
North through center sec 34
- 40 00 1st temporary $\frac{1}{16}$ cor for center sec 34
- 47 00 one branch of Umatilla river 142 lbs across course W
- 63 95 Umatilla river main stream 159 lbs across course NW
- 78 98 $\frac{1}{4}$ sec corner bet nos 27 & 34
West through center sec 26
- 81 00 the $\frac{1}{4}$ sec cor bet nos 26 & 27
North through center sec 27
- 77 80 the $\frac{1}{16}$ sec cor bet nos 27 & 34

Chains Links

- North bet Sec 25 & 26 34 N 16 28 6
- 39 77 Set Stone and post marked for $\frac{1}{4}$ sec cor
- 41 25 O B & N B B S 50° E N 80° W
- 68 06 U S Feed Canal 6 & N
- 79 58 The corner to Sec 23-24-25 & 26
West through center sec 26
- 29 50 O B & N B B S 50° N 80° E
- 81 00 a point 20 lbs S of $\frac{1}{4}$ sec cor
thence E on same line
- 40 57 Set Stone marked and post for center sec 26
thence south through center S $\frac{1}{2}$ sec 26
- 28 5 O B & N B B 68 W
- 40 00 a point 4 lbs south of $\frac{1}{4}$ sec cor
thence north on same line
- 20 00 Set post marked for $\frac{1}{16}$ cor in center S $\frac{1}{2}$ sec 26
from the $\frac{1}{4}$ sec cor bet Sec 26 & 27 1 run N
south bet Sec 26 & 27
- 2 40 O B & N B B 68 W
- 40 12 the cor to Sec 26-27-34 & 35-
south through center sec 27
- 35 85 O B & N B B
- 77 80 a point 25 lbs W of $\frac{1}{4}$ sec cor
thence north on true line
- 19 95 Set Iron Pipe and stake marked for $\frac{1}{16}$ cor in center S $\frac{1}{2}$ sec 27
- 39 90 the center sec 27
East through center sec 34 from center sec 34
- 40 43 the $\frac{1}{4}$ sec cor bet Sec 34 & 35-
From the $\frac{1}{4}$ sec cor bet Sec 1 & 6 on range line bet 33 & 16 28 & 29 6
run north bet Sec 1 & 6
- 40 50 the cor to Sp 3 & 4 N 16 28 & 29 6

Chains Links

South Through center sec 1
 80 50 the $\frac{1}{4}$ sec on lot nos 1 & 2
 West Through center sec 1
 80 12 the $\frac{1}{4}$ sec on lot nos 1 & 2
 North Through center $\frac{1}{2}$ sec 1
 40 74 $\frac{1}{16}$ sec in center E $\frac{1}{2}$ sec 1
 80 20 the $\frac{1}{16}$ sec on N Body N $\frac{1}{4}$ sec 1

John W. Timbrell County Surveyor
 assisted by Jerry Barnhart Chairman
 Chas. Holloway "
 Port Sheehan Flagman