

Survey for J.N. Burgess and Others.

Chains Links

Sec. 18, T. 2 S., R. 32 E. W. M.

Marvin Hutchison }
 Conn Roundtree } chainmen.

April 7, 1916.

Began at Cor. Townships 1 & 2 S. R. 32 E. W. M. and ran South on Township line, which is also a fence line.

- 40.13 fence west.
 80.26 indications of old mound, old fence row East.
 120.41 fence East.
 155.38 marked stone lying loose on ground, this is probably the Cor. Cor. Stone. There is nothing to indicate that this point has ever been accepted as a Cor.
 240.00 temp. pt. Can find no trace of old cor. or one set by Arnold.

— Continued Survey — April 21, 1916.

Reset Cor. sec's 7-8-17-18, set marked Stone & stone mound, in fence line. Old furrows run N & S. indications of old fence South. Thence East on random.

- 25.30 Ravine.
 39.98 Found original Cor. cor. in fence buck. fence N & W. a stone marked 1/4. Returned to Cor. sec's 7-8-17-18 and projected North line of Sec. 17, West.
 40.00 temp. pt. for 1/4 Cor. sec's 18-7 in plowed field.
 40.73 Ravine.
 79.82 fence on range line.
 Began at cor. sec's 7-8-17-18 ran South.
 90.00 temp. point. Can find no trace of 1/4 cor. except intersection of old fence lines.
 80.14 a point 36 lks. West of point of intersection of old furrows E & N. by digging at point of intersection found very small point of old stake. This point has been broken on striking rock. This old stake point is at exact point of intersection of old furrows. There was a few loose rocks piled at this point.
 78.97 a point 359 lks West of stone cor. set by Arnold for Cor. sec's 17-18-19-20.

Chain Links

Began at Cor. set by Arnold for Cor. Sec's 17-18-19+20 ran thence West, along fence line.

40.76 a point 3 LKS S. of $\frac{1}{4}$ Cor. set by Arnold.

43.90 a point 118 LKS North of old $\frac{1}{4}$ cor. stone mound and stone that fits description of Cor. set by Survey of 1864.

82.65 temp. pt.

This makes the distance from the Cor. Secs. 17-18-19+20, accepted as Cor's of 1864 Survey, to $\frac{1}{4}$ Cor. of same survey

40.27 Ground almost level. From $\frac{1}{4}$ Cor. to township line.

30.32 steep descent.

April 22 1916.

Began at $\frac{1}{4}$ cor. Secs. 19+24 on township line, a stone and stone mound which fits description of Cor. set in 1864 survey. fence N+S.

Mr. Fred Hascall says this cor. was at this point long before Arnold made his Survey of 1890. Ran North on true line—descend steep hill.—

40.28 to temp. point from township cor. South.

24.00 This gives a distance of 40.04 for each $\frac{1}{2}$ mile of distance on range line between known and acceptable corners;

40.04 on true line set stone $20 \times 12 \times 8$ marked 3 notches on N+S for Cor. Secs. 18-19 on range line. This is according to proportionate distances from definite Cor's. North+South which I feel positive were set by Survey of 1864. I believe from evidence that original Cor. stood about 54 LKS South and Arnold's Cor. about 30 LKS North.

Thence North on true line.

40.04 set $\frac{1}{4}$ Cor. Stone $20 \times 7 \times 7$ marked $\frac{1}{4}$ on South. raised stone md.

44.78 stone in fence buck no definite figures visible, does not fit description of Cor. cor. no fences E+W. no indications of old acceptance as cor. This is claimed by Mr. Fred Hascall to be Cor. $\frac{1}{4}$ cor.

Cont'd line North.

20.02 $\frac{1}{16}$ cor. set stone marked $\frac{1}{16}$.

Chains Links

- 40.04 Set stone for Cor. Sec's. 7*18 on range line. Stone marked 2 notches on North & 4 notches on south. Tin can under.
- This makes the random west from Cor. Sec's. 7-8-17*18 come out at
- 79.31 a point 21 lks South of Cor. Sec's. 7*18 as established above. Thence East on true line.
- 39.78 Set stone $\frac{1}{4}$ Cor. Stone 20"x6"x5" marked $\frac{1}{4}$ on South. 28 lks. West of fence running N* S. Thence South on N* S. center line Sec. 18-
- 20.00 temp. $\frac{1}{16}$ Cor.
- 40.00 " center.
- 80.46 point accepted as $\frac{1}{4}$ Cor. established by survey of 1864. Set stone marked + to perpetuate old cor. Sec's. 17-18-19*20 as established by survey of 1864. Thence North on true line.
- 40.07 Set $\frac{1}{4}$ Cor. a stone 14"x16"x8" marked $\frac{1}{4}$ on North, raised stone md. old furrow runs North and South and indications of old fence running North and also West, from location of this Cor. Began at above established $\frac{1}{4}$ Cor. Secs. 17*18, sighted on Cor. Sec's 17-18-19*20 and turned 90°- ran thence West on this line as random, along old fence row.
- 39.80 intersect true N* S. center line
- 79.27 a point 68 lks South of $\frac{1}{4}$ Cor. West side of 18 as established. East on true line.
- 19.92 set stone $\frac{1}{16}$ Cor. Thence East.
- 19.56 to center Sec. 18- T. 2 S.; R. 32 E. W. M. Set a stone marked +. From which the S. $\frac{1}{4}$ Cor. Bears South. 40.39 chains.
- " " " N. $\frac{1}{4}$ " " North 40.07 "
- Set a stone for center N. W. $\frac{1}{4}$ Sec. 18 marked +.

Recorded April 29, 1916.

William Bradley
County Surveyor

