

Survey for E. P. Tulloch.

May 9-10-11 1916.

Chains Links

Secs 29 & 32 T. 3 N. R. 32 E. W. M.

Ben Estes & F. A. Potter—Chainmen.

Began at concrete post $\frac{1}{4}$ Cor. sec's 32 & 33 Thence West.

39.86 Concrete post at fence cor. Thence cont'd West.

39.94 Found stone in Road. Set stone marked $\frac{1}{4}$ Glass under. Thence North.80.00 Found stake set by Kimbrell. Set porous basalt rock marked $\frac{1}{4}$.
glass under.Began at $\frac{1}{4}$ cor. sec's. 32 & 33 North on random.

40.00 Could find no trace of cor.

80.33 Found Gov. cor. $\frac{1}{4}$ Sec's. 28 & 29. Which is Gov. stake. Set porous
stone, glass & coal under.Began at $\frac{1}{4}$ cor. sec's. 30 & 29 Thence North.40.37 Gov. Cor. located by fence and road intersection and word of
A. T. Perkins. Set stone 14" x 12" x 6" marked + bottle under.
Thence East on true line between Secs. 20 & 28.40.22 set $\frac{1}{4}$ cor. stone marked $\frac{1}{4}$ bottle under.40.79 fence N & S. a point 20 ~~1/2~~ South of fence cor.80.44 Cor. Secs 20-21-28-29 replaced old stake by stone marked +.
Thence South.40.00 $\frac{1}{4}$ cor. Sec's. 28 & 29.Set center Sec. 29 at exact intersection of center lines N-S $\frac{1}{2}$ E-W.
a stone 18" x 12" x 8" bottle under. From this cor.40.06 West to $\frac{1}{4}$ Cor. Est. by Kimbrell.39.86 East to Gov. $\frac{1}{4}$ cor.40.18 North to $\frac{1}{4}$ cor Est. by this survey.40.09 South to $\frac{1}{4}$ " " " Kimbrell.Willard Bradley.
County Surveyor.