

Survey for Mr. Medesto

Block 4 - Lots 3-4-5-6-11 $\frac{1}{4}$ of 2 Lots in Block North. Town of Reith, Ore.

Starting at monument in center of Main St. of Reith, which is a rock marked X and set 15" in the ground, I sight on monument N 55°-43'-35" E - 860 ft. which is also in E of Main St. and is a very hard rock not very plainly marked as it chips badly. Then I turn a 90° angle and run N 24°-16'-25" E - 30 ft. to be on the Lot line. I then backsight on monument and turn a 90° angle so as to sight along the lot line. Thence ^S 56°-43'-35" along line

88 ft. Set stake for cor. of lot 3 of Block 4

114 ft. Set stake for cor. of lot 3-4 of Block 4

136 ft. Set stake for cor. of lots 4-5 of Block 4. by hydrant which is on West line of E. house.

Thence by a 25° curve to left

26.4 ft. to cor. of lots 5-11 - deflection angle - 3°-34' L Thence by 25° curve to left

44.4 ft. to pt. of tangent on lot line - deflection angle 8°-7' L.

Thence sight on cor. of Lots 4-5 turn angle to Left 8°-7' and plunge telescope and prolong line.

27.78' set stake for cor. to Lots 10-11 Thence N 25°-46'-25" W

77.44' Set stake for cor. of lots - 6-7-9-10

167.44' Set stake for cor. of lots - 6-7

207.44' Set stake 5' N. of Lot on N. side of St. Thence set up over cor. to lots. 6-7 and turn a 90° angle left from back sight and run. N 64°-13'-35" E

97.4 ft. Set stake for cor. of lots. 5-6

77.42 ft. Set stake for cor. of lots 5-4 Then set up over stake on N side of road and 50' from cor. of Lots 6-7 and back sight on said cor. and turn a 90° angle to left

5' set eor. of lot.

55' set cor. of Lot.

105' a point 1.21 ft. N. of cor. of Lot.

Set up over 1st Lot stake and turn angle of 90° and set stake 76' for NW cor. of lot.

Set up over this stake turn 90° angle.

50' set stake for cor. of lot.

111' set stake for cor. of lot. Thence set up over cor. of lots. 3-4 on S. line and run N 24°-16'-25" W

122.4 ft. Set cor. of lots 3-4. Thence set up over cor. of lots 2-3 on S line and run N 11°-15'-15" W

109.78 ft. Set stake for cor. of lots - 2-3 of Block 4

Quincy E. Perry
Deputy County Surveyor
Dec. 13-1918

RECORD OF SURVEY No. 416

Survey for Fred Hascall by J. B. Runyan.

SPERRY, GLASS & FRYHOVER COMPANY, PRINTERS AND PUBLISHERS, TOLEDO, OHIO

Chains Links

Sec. - 18 - Tp. 2 S - R 32 E. W. M.

Nov. 30th 1918

Beginning of the cor. to Sec. 18-19-13-24 which is a basalt rock 14 x 12 x 6 1/2 ins. set 10 ins. in the ground and was set by Arnold and is 2 1/2 lks. N. of Cor. set by Bradley and is accepted as the true corner by Mr. Hascall and Mr. Runyan, I run North

10 20

Stanley Creek

11.00

Cor. of Hascalls house.

15.00

Road NW-SE and bottom of hill.

Ascend.

40.00

a point 20 lks. N of 1/4 cor. set by Bradley.

60.00

set stake on N + S fence line from whence 1/16 cor. set by Bradley is North 9.93 chs.

Thence Due East staking line to N + S. fence in center of section. This line was agreed upon and accepted as the dividing line of their properties. (Hascall + Runyan)

From the point where East line intersects fence - the center of the section as set by Bradley bears S - 10.60 ch. and W. - 1.52 chs.

There is quite a dispute over the corners of this section. For reference see Map on page 287 of Survey 413-412 by Bradley. See Notes in red for this survey.

Quincy C. Perry
Deputy County Surveyor.
December 9-1918.

