

Survey for Mrs. Jane Nelson-Athens of Reservation Boundary.

Chains Links

Tp. 4N R 34E

Starting at a point 55.50 ch. S. of Sec. Cor. North 12-24 Tp. 4N R 34E. on the Tp. line I ran in the reverse of the Wild Horse line as given by the notes, and find the error of closing on the S. sec. line to be 70 lks. E. of a point 34.40 ch. E. of Sec. cor. West, and 1.05 ch. North. From this it will be seen that the point of the survey that was taken as the Sec. corner was 68 ch. N. of the true line.

Starting at a point on the S. Sec. line of Sec. 24-34.40 E of SW Cor. I ran

North

- | | | |
|-------|--|------------------------------|
| 1 05 | Thence $N 8\frac{1}{4}^{\circ} E$ | |
| 9 60 | Thence $N 39^{\circ} E$ | |
| 13 50 | Thence $N 69\frac{1}{2}^{\circ} E$ | I set a stake at each point. |
| 4 20 | Thence $S 86\frac{1}{2}^{\circ} E$ | |
| 11 00 | Thence $N 63^{\circ} E$ | |
| 8 50 | Thence $S 78\frac{1}{4}^{\circ} E$ | |
| 10 00 | Thence $N 58^{\circ} E$ | |
| 4 90 | to a point 70 lks. W. of a point 55.50 ch. south of Sec. Cor. north, Thence to this point | |
| 70 | Thence Due South along this Tp. line | |
| 26.25 | to \perp of Road thence Due W. along said road | |
| 46.90 | to point of beginning. | |

Area = 101.2 Acres. Railroad cuts out about 6 acres.

Area of road on E = strip $25.10 \times .45 = 11.4$ Acres.

Note - The original line was run in with a compass and I used a transit so there may be some error between the two lines as run. Mrs. Nelson didn't want to pay for having the lines checked to see if they were right so I let it go at that.

Surveyed Feb. 17-1919

Arthur E. Perry
County Surveyor.