

Survey for Dr. E. O. Parker - Casteel Bros. and Schmidt

March 13-14-1919.

Bill Abbot - ch.

Lem Casteel - ch. - Rod

Starting at the point supposed to be the $\frac{1}{4}$ cor. on Base Line for Sec. 5

Tp. 15 N 31 E - I chain West.

24.25 To cor. of fence running S.

33.54 To cor. of fence running N.

43.26 To rock at cor. of fence running S.

Starting at the same point and running East

37.40 Rock that answers description for Sec. Cor. Stone. - It has been moved. marks no very plain.

47.00 Fence running North

117.25 Rock $17'' \times 14'' \times 8''$ - cor. to Sec. 5-4 Tp. 15 N 31 E.157.70 Fence running S. - Rock - $25'' \times 14'' \times 6''$ 197.70 fence running South - Rock $12'' \times 8'' \times 6''$

206.80 Rock Cor. to Sec. 34-35 - Tp. 14 N 31 E.

As the total distance between the Sec. Cor. for South of base line is 14.11 ch. long - the dist. bet. Sec. Cor's. is 80.56 ch. and the $\frac{1}{4}$ cor. set $\frac{1}{2}$ the dist. bet. The jog for the N. cor's. is 9:30 ch. E. of S. Cor's.

Beginning at Sec. Cor. 3-4 on the base line for Tp. 15 N 31 E. which is a rock.

 $17'' \times 14'' \times 8''$ set in ground marked X on top I run West on base line.

71.36 Set Rock for Sec. Cor. - 32-33 on N - Marked 11 on W and 111 on E.

80.56 Reset Rock on line for Sec. 4-5-5 Marked 11 on W - 111 on E.

120.84 Set Rock on line of $\frac{1}{4}$ cor. to Sec. 5 (M) $\frac{1}{4}$.140.98 Set Rock for W $\frac{1}{4}$ cor. to sec. 5 Marked X

151.21 Set Rock marked 1 on W - 111 on E for Sec. Cor. to Sec. 31-32 on North

161.11 Cor. to Sec. 5-6 - Tp. 15 N 31 E.

Thence starting at Sec. Cor. on Base line to Sec. 32-33 I turn angle of $90^{\circ} 08'$ from West and run North.

40.00 could not find $\frac{1}{4}$ cor.

80.40 old cor. rock to sec. 32-33-27-28 Dug. down and found remains of old stake. Remarked rock 1111 on N & 1111 on E - 1 on S.

40.14 Returned back and set a rock for $\frac{1}{4}$ cor. marked $\frac{1}{4}$ on top from each cor.

Thence turn angle of $90'$ and run East.

40.14 Set rock for C. of Section.

D. E. O. Parker - Central Bros. & Schmidt.

Chain Links

Tp. 13 R 31 E

Starting at the $\frac{1}{4}$ sec. cor. on base line for Sec. 5 I chain South along fence
 82.08 To east-west line on south side of section. No trace of rock cor. Then starting
 at the fence cor. I chained W. along fence
 40.40 to old sect. cor. Rock not very plainly marked. Dug in ground and found old rotten stone
 Remarked rock. Thence east along fence
 20.20 Set rock marked $\frac{1}{16}$ for $\frac{1}{16}$ sec. cor.
 40.40 Cor. of fence Set rock marked $\frac{1}{4}$ for cor.
 Thence along fence line north.
 82.08 a point 44' W of $\frac{1}{4}$ cor.

Then I corrected line by setting the 42.00 ch. mark 25ft. east.

Reuben E. Perry,

County Surveyor.