

Citizen's Bank of College Place - Collins Tract - T6N, R35EWM

Relocated $\frac{1}{4}$ corner common to sections 26 & 35, T6N, R35EWM, from I.P. set by Aubrey Perry, Co Surveyor, in 1912. Checked position by 5' Locust (R.P.) standing 37' NE of $\frac{1}{4}$ corner, and by asserted positions of two destroyed locusts originally standing 45' E.N.W. and 47' E. SW of corner.

From Sta. 5781.66 (OWEN Co), corner common to Sections 34 and 35, T6N, and Sections 2 & 3, T5N, R35EWM, lies 1543.71 distant, line making an angle of 66° 54' with OWEN center-line.

From Sta. 496.100 (OWEN Co) corner between Section 36, T6N, and Section 1, T5N, R35EWM, lies 735.3' distant, line making an angle of 45° 28' with OWEN Co. center-line.

Beginning at corner common to Sections 34 and 35, T6N and Sections 2 and 3, T5N, R35EWM on true line, 1 run -

111-112 735.3' to corner between Sections 36, T6N, and 1, T5N, R35EWM.

Thence from said corner between Section 36, and Section 1, 1 run,

111-112 1000' to locate corner between Section 35, T6N, and Section 2, T5N, R35EWM said corner being 1000 feet west of center-line of Oregon-Washington Highway.

Thence North on North and South center-line of Section 35,

1127.42 (one-half the average length of South half of the East and West boundaries of Section 35), to locate NW cor. of SW $\frac{1}{4}$ of SE $\frac{1}{4}$ of Section 35, T6N, R35EWM.

Thence ~~North~~ South on said center-line

938.00,

Thence East

158.00, set iron pipe,

Thence North parallel to center-line of said section

158.00, set iron pipe,

207.24, set iron pipe.

F. B. Hayes

Frank B. Hayes, County Surveyor
by *F. B. Hayes* deputy



Walter Ulrich, Inc.

John Martin, Inc.

