

mkd $\frac{1}{4}$ S on N face. 16" Pine
bears N 60° W 65 lbs mkd

$\frac{1}{4}$ S. B.T. 18" Pine bears S 15° E 55 lbs
mkd $\frac{1}{4}$ S B.T.

80.00 to cor sect 8, 9, 16, 17

North bet secs 8 & 9. Var 22° 45' E

40.00 Set basalt stone 9" x 8" x 8" - 6" in ground

mkd $\frac{1}{4}$ S on W face from which
a 12" Pine bears N 43° W 45 lbs

mkd $\frac{1}{4}$ S. B.T. 24" Pine bears
S 45° E 145 lbs mkd $\frac{1}{4}$ S B.T.

80.00 Stone 10 x 8 x 8 - 7" in ground, for
cor to secs. 4, 5, 8, 9. mkd 5 notches
on S & 4 on E edges; raised mound
of stone over it.

S 89° - 49' W bet secs 4 & 9.

40.00 Stone 10 x 12 x 6" - 8" in the ground
mkd $\frac{1}{4}$ on N side, mound of stone