

corner found next day 39.07 ch north from sec
cor.

79.66 Searching diligently for signs of a corner,
intersect section line 35 links west
of a mound of rock which I take to
be the cor common to secs 29, 30, 31, 32

From sec cor common to secs 29, 30, 31, 32
I run west on an offset line 34 links
north of section line by turning $87^{\circ} 29'$
left from north random line. Met secs
31 & 32.

40.07 Intersect $\frac{1}{4}$ sec line 97 links north of
 $\frac{1}{4}$ cor which is a mound of rock
The stone marked $\frac{1}{4}$ had rolled down
hill about a chain or little more & I
brought it back to the mound &
built up a large mound of stone.
From the $\frac{1}{4}$ cor common to secs 30 & 31

I run west correcting my line $1^{\circ} 23'$ toward
the south.

Aug 30
1917.

85.90 Intersect section line 14 links north of