

35 Oct 18, 1917. Sub T1NR34E.

From temp. cor. of sec. 4.5, 8+9, set by Mr. Campbell, described on Page 30, I measure North 63 lks. and West 47 lks. to a fence corner, bears N+W, apparently set at the original point for Cor of Secs. 4, 5, 8+9, but I can find no trace of corner.

Backsight on fence about 1/4 mi. South thence
Thence S 89° 45' E bet Secs. 4+9. Va. 2 1/4 E

.60 Pendleton La Grand wagon road N 60° E

20.00 Set temp cor. (Correction 1 1/2 lks. E. 15 1/2 lks N)

20 11 1/2 Set lath in red stone for 1/16 cor

40.23 Fall 37 lks. S. of 1/4 cor, a basalt, 6x8x6 ins above ground in ^{remains of} mound of stone. Leave corner as found and raise mound of stone north of cor.

Thence East

20.00 Set temp cor. (Correction 14 lks. E. + 9 1/2 lks N)

20.14 Set 1/16 cor. (9 1/2 N - 14 E)

40.28 Fall 19 lks S of cor of sec. 3, 4, 9+10, a basalt stone properly marked, in mid of stone
Raise red stone W. of cor.