

45 N bdy T 1 N R 34 E

From 1/4 cor bet secs. 6 + 31 run west.
 20. Set 1/16 cor. Spring bears S E about 4 ch.
 23. Spring about 50 lks N of line.
 29. Spring just south of line.
 29.50 Gulch N 60° W.

44.52 Cor of Tps 1 + 2 N Rs 33 + 34 E bears
 S or 21 lks. a basalt (with pits + md.)
 8 x 10 x 6 ins above ground,
 marked with 6 notches on N + W
 (X) on top. Pits in each sec.
 I mark 6 notches on E + S sides
 and raise Md Stone south of cor.
Thence South

20 Set 1/16 cor. (5W - 70 S)

40.50 Gulch N 60° W.

41.40 1/4 cor bears W, 10 lks. A basalt
 in md stone.

Thence East through Deer 6

Gulch N 60° W
 Set temp 1/16 cor. (15 lks N - 12 W)

44.00 Set temp 1/4 cor at center. (33 lks N - 2 W)

43.98
 64.00 Set temp 1/16 cor. (46 lks N - 24 W)

83.54
 83.52 1/4 cor bet secs 5 + 6 bears N, 60 lks.

39.58