



3/14/18. From pt. for cor of 3.4.9 & 10, in run run N. 30° W. toward well, recorded at 63.00 ch. on line bet 3 & 4. (200 ft)  
 3.03 N. bank of Minitela River. Set stone for W.C. 300 ch N of pt marked 1111 on S - 111 on E. WC 200 ft on S

Man. 14, 1918 Also set for W.C. 30 13E  
 and 30 ft W. of stone  
 13.20 Well on line, recorded at 63.00 ch on line bet. 3 + 4 run South, or 12.70 ch N. of cor of sec 3.4.9 & 10.  
 Thence NO 45° W.  
 5.50 NW cor of porch on N side of house bears East 12 lks. (Recorded at 57.50 on line run S. bet 3 & 4 on house bears E. 12 lks.)  
 7.30 Set 1/8 cor.  
 Thence continue NO 45° W  
 20. Set for 1/8 cor in road.  
 55.34 Cor of 3 + 4 bears S 100 lks.  
 Mar. 6 From 1/4 cor bet 3 + 4 run E by rd. 5 1/2 E. 18 S  
 20 Set 1/16 cor  
 40.11 Center Sec 3 bears S. 36 lks.  
 40. Set Wm A Wilson against fence corner at corner point established by Kimball.  
 40.43 Fence N + S. Fence cor. N + S and E + W bears S 36 lks.  

88	88
36	17
352	105

 60. Set  
 60.41 Fence cor. 6 + W. + S. bears S. 50 lks  
 70.61 Fence bet 1/32 cor. 2 + W fence bears S. 80 lks  
 80.81 N + S fence. Fence cor. N. S + W, bears South. 92 lks  
 80.27 1/4 cor bet 203 bears S. 64 lks.  
 80.26 From point 17 lks S. of fence cor. run North  
 36-63 Fence cor. N. S. + E. E. bdy Sec 3  
 35.84  
 Mar. 15 From 15 - S. 3 run East  
 20.20 Set iron post for 1/8 cor.  
 40.40 Set stone in road for 1/16 cor + iron post 30 ft N for W.C.  
 60.60 Set stone under fence on S. side of road  
 80.80 1/8 cor at 12 S. 3 bears N. 6 lks.